

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Mike Wasinger of Knight Casing Pulling Co., has this date requested permission to plug the following described well:

Mr. Wasinger guarantees payment of the plugging fee.

Operator's full Name: James M. Stewart,

Complete Address: 608 Union Center, Wichita, Kansas.

Lease Name: Bollig Well No. 1

Location: 100' E of CNE-NW Sec. 28 Twp. 9 Rge. (E)(W) 25

County Graham Total Depth 4075' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Wasinger was instructed to plug the well as follows:

252'--8 5/8" Surface pipe, cement circulated.  
4072'--5 1/2" Production casing cemented with 100 Sx. Well plugged back to 4025'. Top perforations @ 3905'.

Sand well back to 3890' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well using 20 Sx. gel with 5 sacks hulls in initial gel then follow with 100 Sx. cement then 22 sacks gel followed with 20 Sx. cement, then 4 sacks gel and follow with 8 Sx. cement.

RECEIVED  
STATE CORPORATION COMMISSION  
9-12-67  
SEP 12 1967

Very truly yours,

Conservation Division Agent

CONSERVATION DIVISION  
Wichita, Kansas