

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
4-4-72
APR 4 - 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Albert Unruh of South-West Casing Pulling, has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Bankoff Oil Company,

Complete Address: 1119 Sherman, Great Bend, Kansas.

Lease Name: Bollig Well No. 1

Location: SW-SW-SW Sec. 28 Twp. 9 Rge. (E)(W) 25

County: Graham Total Depth 4090' Oil Well

Gas Well Input Well ^{RTKLL} SWD Well D & A Lost Hole

Mr. Unruh was instructed to plug the well as follows:

231'--8 5/8" Surface casing, cement circulated with 150 Sx.
4085'--4 1/2" Production casing cemented on bottom with 150 Sx. Well
plugged back to 4050'. Top perforations from 3861' to 3864'.

Push plug to 3850', sand well back to 3825' and set 4 sacks cement with
dump bailer. Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 30
sacks gel and 150 Cu. Ft. cement ~~fill~~, staged.

Very truly yours,

M. L. Nichols
Conservation Division Agent