

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION10-12-70
OCT 12 1970CONSERVATION DIVISION
Wichita, KansasVERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Victor Justus of Leben Drilling, Incorporated has this date requested permission to plug the following described well:

Mr. Justus guarantees payment of the plugging fee.

Operator's full Name: Leben-Bankoff,

Complete Address: Drawer #2479, Tulsa, Oklahoma.

Lease Name: Brungardt Well No. B-1

Location: NE-NE-SE Sec. 32 Twp. 9 Rge. (E)(W) 25

County: Graham Total Depth 4115' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Justus was instructed to plug the well as follows:

209'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1075'.

Circulate hole with heavy mud. Pull DP to 1300' and displace 100 Sx.
cement thru DP. Pull DP to 245' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent