



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
10-26-70
OCT 26 1970
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Norman Cook of Abercrombie Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Abercrombie Drilling, Incorporated,

Complete Address: 801 Union Center Building, Wichita, Kansas.

Lease Name: Pfeifer Well No. 1

Location: CSW-NW-NW Sec. 32 Twp. 9 Rge. (E)(W) 25

County: Graham Total Depth 4090' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cook was instructed to plug the well as follows:

212'--8 5/8" Surface casing, cement circulated with 175 Sx. (6 3/4" Hole).
Top of Dakota section @ 1100'.

Circulate hole with heavy mud. Pull DP to 1325' and displace 65 Sx.
cement thru DP. Pull DP to 220' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

M. L. Nichols
Conservation Division Agent