

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

AUG 28 1967
8-28-67

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Claude Norwood of Leben Drilling, Inc., has this

date requested permission to plug the following described well:

Mr. Norwood guarantees payment of the plugging fee.

Operator's full Name: Bankoff Oil Co. & Leben Drilling, Inc.

Complete Address: Box # 2479, Tulsa, Oklahoma.

Lease Name: Spies Well No. 1

Location: 150' West of CNE-NW Sec. 35 Twp. 9 Rge. (E)(W) 25

County Graham Total Depth 4085 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Norwood was instructed to plug the well as follows:

251'--8 5/8" Surface pipe, cement circulated with 150 Sx. Dakota section from 1780' to 1980'.

Circulate hole with heavy mud, plu DP to 2000' and displace 100 Sx. cement thru DP. Pull DP to 250' and displace 20 Sx. cement thru DP. Pull DP. set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent