

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
5-7-71  
MAY 7 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Dean Ulrich of Murfin Drilling Company has this date requested permission to plug the following described well:

Mr. Ulrich guarantees payment of the plugging fee.

Operator's full Name: Murfin Drilling Company,

Complete Address: 617 Union Center, Wichita, Kansas.

Lease Name: Spies Well No. 1

Location: SE-SE-NE Sec. 35 Twp. 9 Rge. (E)(W) 25

County: Graham Total Depth 3836' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Ulrich was instructed to plug the well as follows:

210'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 900'.

Circulate hole with heavy mud. Pull DP to 1125' and displace 100 Sx.  
cement thru DP. Pull DP to 215' and displace 25 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

W. L. Nichols  
Conservation Division Agent