

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent) STATE CORPORATION COMMISSION

RECEIVED

9-27-74
SEP 27 1974CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Reiter of Murfin Drilling Company has this
date requested permission to plug the following described well:Mr. Reiter guarantees payment of the plugging fee.Operator's full Name: Zenith Drilling Corporation,Complete Address: Suite 600, 200 West Douglas, Wichita, Kansas.Lease Name: Haffner Well No. 2Location: SW-SW-NW Sec. 19 Twp. 9 Rge. (E)(W) 27County: Sheridan Total Depth 4135' Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Reiter was instructed to plug the well as follows:260'--8 5/8" Surface casing, cement circulated with 175 Sx.Top of Dakota section @ 1175'.Circulate hole with heavy mud. Pull DP to 1400' and displace 110 Cu. Ft. cement thru DP. Pull DP to 275' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent