

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 11-18-68
 NOV 18 1968
 CONSERVATION DIVISION
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Joe Clark of Southwest Csg. Pulling Co. Inhas this date requested permission to plug the following described well:

Mr. Clark guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Company,

Complete Address: 1130 Wichita Plaza Building, Wichita, Kansas.

Lease Name: Corke Well No. 1

Location: SE-SE-SE Sec. 24 Twp. 9 Rge. (E)(W) 26

County: Sheridan Total Depth 4131 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Clark was instructed to plug the well as follows:

227'--8 5/8" Surface casing, cement circulated. (6 1/2" Hole).

4129'--4 1/2" Casing cemented on bottom with 100 Sx. Top perforation @ 4064'. No plug back indicated.

Sand back to 4050' and set 3 Sx. cement with Dump Bailer. Pull 4 1/2" Casing and squeeze well with 20 sacks gel plus 3 sacks hulls and 100 Sx. cement staged.

Very truly yours,

Conservation Division Agent