



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
6-18-70
JUN 18 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Delbert Adams of Forbes Casing Pulling Co. Inc has this date requested permission to plug the following described well:

Mr. Adams guarantees payment of the plugging fee.

Operator's full Name: American Drilling Corporation,

Complete Address: 360 Sutton Place, Wichita, Kansas.

Lease Name: Ochs Well No. 1

Location: NE-NW-NW Sec. 24 Twp. 9 Rge. (E)(W) 28

County: Sheridan Total Depth 4167 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Adams was instructed to plug the well as follows:

280'--8 5/8" Surface casing, cement circulated with 200 Sx.
4163'--4 1/2" Production casing cemented on bottom with 150 Sx. No plug back. Top perforations from 3908' to 3914'.

Push plug to 3875', build sand bridge to 3850' and set 3 Sx. cement with dump bailer. Pull 4 1/2" casing and squeeze with 5 sacks hulls, 35 sacks gel and 135 Sx. cement staged.

Very truly yours,

H. L. Nichols
Conservation Division Agent