



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
9-17-74
SEP 17 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Reiter of Murfin Drilling Company has this

date requested permission to plug the following described well:

Mr. Reiter guarantees payment of the plugging fee.

Operator's full Name: Zenith Drilling Corporation,

Complete Address: Suite 600, 200 W. Douglas, Wichita, Kansas.

Lease Name: Ochs Well No. 2

Location: SE-SW-NE Sec. 24 Twp. 9 Rge. (E)(W) 28

County: Sheridan Total Depth 4155' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Reiter was instructed to plug the well as follows:

253'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1225'.

Circulate hole with heavy mud. Pull DP to 1450' and displace 110 Cu. Ft.
cement thru DP. Pull DP to 275' and displace 30 Cu. Ft. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to
bottom of cellar.

Very truly yours,

H. L. Dehob
Conservation Division Agent