



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 5-13-63  
 MAY 13 1963

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

CONSERVATION DIVISION  
 Wichita, Kansas

Dear Sir:

Mr. Elmo Finch of Pipe Pullers Incorporated has this

date requested permission to plug the following described well:  
C & G Drilling Co.,

Mr. Finch guarantees payment of the plugging fee.

Operator's full Name: C & G Drilling Company,

Complete Address: 107 Rule Building, Wichita, Kansas.

Lease Name: Corke Well No. 1

Location: CNW-NW Sec. 24 Twp. 9 Rge. (E) (W) 26

County Sheridan Total Depth 4170 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Finch was instructed to plug the well as follows:

239' 8 5/8" surface pipe, cement circulated w/150 Sx.  
4168' 5 1/2" cemented w/100 Sx. Plugged back to 4140', top  
perforations from 4063' to 4066'.  
Sand well back to 3900', set plug and bridge and 5 Sx cement  
with dump bailer. Pull 5 1/2" casing to 550', circulate heavy gel  
mud and displace 20 Sx cement thru 5 1/2". Pull 5 1/2" to 210' and  
displace 20 Sx cement thru 5 1/2". Pull 5 1/2", set bridge and 10 Sx  
cement to bottom of cellar.

Very truly yours,

N. L. Nichols  
 Conservation Division Agent