

State of Kansas



ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION
(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
7-12-68
JUL 12 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sylvester Fickel of Red Tiger Drilling Company has this date requested permission to plug the following described well:

Mr. Fickel guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management, Incorporated,

Complete Address: 1515 Wichita Plaza Building, Wichita, Kansas.

Lease Name: Corke Well No. 1

Location: 440' FEL & 2200' FNL Sec. 24 Twp. 9 Rge. (E)(W) 26

County: Sheridan Total Depth 4150 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Fickel was instructed to plug the well as follows:

225'--8 5/8" Surface pipe, cement circulated with 165 Sx.
Top of Dakota section @ 1125'.

Circulate hole with heavy mud. Pull DP to 4450' and displace 100 Sx.
cement thru DP. Pull DP to 240' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

H. L. Dehols
Conservation Division Agent