



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
1-15-73
JAN 15 1973
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Bill Rowe of Slawson Drilling Co., Inc., has this date requested permission to plug the following described well:

Mr. Rowe guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson,

Complete Address: 408 One-Twenty Building, Wichita, Kansas.

Lease Name: McFadden Well No. A-1

Location: SE-NE-NE Sec. 9 Twp. 9 Rge. (E)(W) 27

County: Sheridan Total Depth 4030' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rowe was instructed to plug the well as follows:

285'--Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 1125'.

Circulate hole with heavy mud. Full DP to 1350' and displace 110 Cu. Ft. cement thru DP. Pull DP to 310' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent