

State of Kansas



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)RECEIVED  
STATE CORPORATION COMMISSION

DEC 4 - 1972

CONSERVATION DIVISION  
Wichita, KansasJ. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Sylvester Fickel of Red Tiger Drilling Company has this  
date requested permission to plug the following described well:Mr. Fickel guarantees payment of the plugging fee.Operator's full Name: L. G. Stephenson,Complete Address: 360 Sutton Place, Wichita, Kansas.Lease Name: Ochs Well No. 1Location: SW-NE-NE Sec. 24 Twp. 9 Rge. (E)(W) 28County: Sheridan Total Depth 4130' Oil Well Gas Well  Input Well  SWD Well  D & A X Lost Hole Mr. Fickel was instructed to plug the well as follows:266'--8 5/8" Surface casing cement circulated with 185 Sx.  
Top of Dakota section @ 1150'.Circulate hole with heavy mud. Pull DP to 1375' and displace 110 Cu. Ft.  
cement thru DP. Pull DP to 275' and displace 30 Cu. Ft. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to  
bottom of cellar.

Very truly yours,

Conservation Division Agent