

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
3-22-74
MAR 22 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sylvester Fickel of Red Tiger Drilling Company has this date requested permission to plug the following described well:

Mr. Fickel guarantees payment of the plugging fee.

Operator's full Name: Beren Corporation,

Complete Address: 1130 Vickers KSB&T Building, Wichita, Kansas.

Lease Name: Mills Well No. 1

Location: NW-SW-SE Sec. 17 Twp. 9 Rge. (E)(W) 26

County: Sheridan Total Depth 4050' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Fickel was instructed to plug the well as follows:

301'--8 5/8" Surface casing, cement circulated.

Top of Dakota section @ 1045'.

Circulate hole with heavy mud. Pull DP to 1300' and displace 110 Cu. Ft. cement thru DP. Pull DP to 310' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

R. G. Nichols
Conservation Division Agent