

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 125-31767-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 8/30/08.

Well Operator: Deer Run Oil Lease, LLC KCC License #: 33348
(Owner / Company Name) (Operator's)

Address: 2322 CR 1425 City: Caney

State: Kansas Zip Code: 67333 Contact Phone: (620) 879 - 2337

Lease: A. J. Melander Well #: DRPT#3 Sec. 24 Twp. 34 S. R. 14 ☒ East ☐ West

SE - NW - SE - NW Spot Location / QQQQ County: Montgomery

3334 Feet (in exact footage) From ☐ North / ☒ South (from nearest outside section corner) Line of Section (Not Lease Line)

3483 Feet (in exact footage) From ☒ East / ☐ West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: ☒ Oil Well ☐ Gas Well ☐ D&A ☐ Cathodic ☐ Water Supply Well
☐ SWD Docket # _____ ☐ ENHR Docket # _____ ☐ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 7" Set at: 22.6 Cemented with: 9 Sacks

Production Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

List (ALL) Perforations and Bridgeplug Sets: _____

Elevation: 882 (☐ G.L. / ☐ K.B.) T.D.: 777' PBTD: _____ Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: ☒ Good ☐ Poor ☐ Casing Leak ☐ Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): _____

Is Well Log attached to this application as required? ☒ Yes ☐ No Is ACO-1 filed? ☐ Yes ☐ No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Jim Nunneley

Phone: (620) 879 - 2337

Address: 2322 CR 1425 City / State: Caney, Kansas 67333

Plugging Contractor: Consolidated Oil Well Services, LLC KCC License #: 31440
(Company Name) (Contractor's)

Address: PO Box 884, Chanute, KS 66720 Phone: (620) 431 - 9210

Proposed Date and Hour of Plugging (if known?): 9/23/08 @ 1:30 PM

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 9/23/08 Authorized Operator / Agent: [Signature]
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

* Well Plugged - KCC - PKT

dist 3
PKT

DRILLERS LOG

API NO. 15-125-31767-00-00 S. 24 T. 34 R. 14 E. W.

OPERATOR: DEER RUN OIL LEASE, LLC LOCATION: SE-NW-SE-NW

ADDRESS: 2322 CR 1425, CANEY, KS 67333 COUNTY: MONTGOMERY

WELL #: DRPT # 3 LEASE NAME: A. J. MELANDER

FOOTAGE LOCATION: 3334 FEET FROM (N) (S) LINE 3483 FEET FROM (E) (W) LINE

CONTRACTOR: FINNEY DRILLING COMPANY GEOLOGIST: JIM NUNNELEY

SPUD DATE: 8/30/2008 TOTAL DEPTH: 777

DATE COMPLETED: 9/2/2008 OIL PURCHASER: CMT

CASING RECORD

PURPOSE	SIZE OF HOLE	SIZE OF CASING	WEIGHT LBS/FT	SETTING DEPTH	TYPE CEMENT	SACKS	TYPE AND % ADDITIVES
SURFACE:	12 1/4	7	19	22.6	I	9	SERVICE COMPANY
PRODUCTION:	5 7/8	N/A	N/A	N/A	N/A	N/A	PLUGGED WELL

WELL LOG

CORES: NO CORES WERE TAKEN

RECOVERED: N/A

ACTUAL CORING TIME: N/A

RAN:

RECEIVED

MAR 17 2009

KCC WICHITA

FORMATION	TOP	BOTTOM
TOP SOIL	G.L.	3
CLAY	3	12
SHALE	12	14
LIMESTONE	14	15
SHALE	15	17
LIMESTONE	17	20
SHALE	20	22.6
SHALE	22.6	38
LIMESTONE	38	39
SHALE	39	42
LIMESTONE	42	44
SHALE	44	46
LIMESTONE	46	48
SHALE	48	50
LIMESTONE	50	56
SHALE	56	178
LIMESTONE	178	186
SAND & SHALE	186	190
SAND	190	230
LIMESTONE	230	231
SAND	231	274
LIMESTONE	274	275
HALE	275	277
LACK SHALE	277	281
AND & SHALE	281	314
HALE	314	325
AND	325	353
MESTONE	353	356
LACK SHALE	356	365

FORMATION	TOP	BOTTOM
SAND	365	382
SAND & SHALE	382	459
SHALE	459	480
SAND & SHALE	480	526
LIMESTONE	526	530
BLACK SHALE	530	534
LIMESTONE	534	536
SHALE	536	542
LIMESTONE	542	544
SHALE	544	561
SAND & SHALE	561	606
BLACK SHALE	606	610
LIMESTONE	610	611
BLACK SHALE	611	617
LIMESTONE	617	619
SAND & SHALE	619	634
LIMESTONE	634	636
SHALE	636	638
LENAPAH LIMESTONE	638	646
GAS SAND	646	648
SAND & SHALE	648	712
ALTAMONT LIMESTONE	712	744
SAND & SHALE	744	748
SAND	748	752
SAND & SHALE	752	759
SAND	759	777 T.D

DRY HOLE