

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15-065-018400001 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date May 8, 1961

Well Operator: The Dane G. Hansen Trust KCC License #: 5285
(Owner/Company Name) (Operator's)

Address: P. O. Box 187 City: Logan

State: Kansas Zip Code: 67646 Contact Phone: (785) 689-4816

Lease: Gano Well #: 5 Sec. 6 Twp. 10 S. R. 23 East West

NW - NW - NW Spot Location / QQQQ County: Graham

4950 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

4950 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # E13,102-0002 Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 207' Cemented with: 140 Sacks

Production Casing Size: 5 1/2" Set at: 4024 Cemented with: 500 Sacks

List (ALL) Perforations and Bridgeplug Sets: 3868-71; 3948-56; 3964-72

Elevation: 2450 (G.L. / K.B.) T.D.: 3977' PBTD: _____ Anhydrite Depth: 2066'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): See Attached Documents

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Richard L. Wallgren, Sr.

Phone: (785) 689-4816

Address: P. O. Box 187 City / State: Logan, Kansas 67646

Plugging Contractor: Swift Services, Inc. KCC License #: 32382
(Company Name) (Contractor's)

Address: P. O. Box 466, Ness City, KS 67560 Phone: (785) 798-2300

Proposed Date and Hour of Plugging (if known?): 3-10-09 10:00 AM

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 3/13/09 Authorized Operator / Agent: _____

Richard L. Wallgren, Sr. (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*well plugged - KCC PKT

RECEIVED
MAR 18 2009
KCC WICHITA

JOB LOG

SWIFT Services, Inc.

DATE 3-10-09 PAGE NO. 7

CUSTOMER D.G. HANSEN TRUST WELL NO. 5-125 LEASE GARD JOB TYPE PTA TICKET NO. 15716

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL/GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	1000							ON LOCATION
								2 7/8 x 5/2 TOC = 1984' IN 5/2
	1030	4	48	✓		500		MAX 180 SKS CPMWT - CIRCULATE CMT - SURFACE
								PULL TUBING OUT WELL
	1200		5 1/2	✓				TOP OFF WELL 20 SKS CPMWT
								WASH TRUCK
	1300							JOB COMPLETE
								THANK YOU WAVE, BEST, DAVE

RECEIVED
MAR 10 2009
KCC WICHITA

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock,
 Wichita, Kansas


15-065-01840

Company- D. G. HANSEN
 Farm- Gano No. 5

SEC. 6 T. 10 R. 23W
 NW NW NW

Total Depth. 4026'
 Comm. 5-8-61 Comp. 5-18-61
 Shot or Treated.
 Contractor. C-G Drig.
 Issued. 10-7-61

County Graham
 KANSAS



CASING:
 8 5/8" 207.20'
 5 1/2" 4025'

Elevation. 2455' RB

Production. 85 BOPD

All meas. from top of RB. Figures indicate Bottom of Formations.

shale-sand	1200
shale	1610
sand	1820
red bed	2066
Anhydrite	2104
shell-shale	2300
shells-shale	2350
shale-lime	2640
lime-shale	3490
shale-lime	3680
lime-shale	3755
lime	3842
lime-shale	3870
lime	3930
lime-shale	3956
lime	3975
lime-shale	4026
Total Depth	

TOPS: SCOUT	
Anhydrite	2066
Topeka	3542
Heebner	3754
Toronto	3777
Kansas City	3794
Base Kansas City	4020

DST 3818-3842'
 DST 3858-3870'
 DST 3938-3956'
 DST 3952-3975'
 DST 3974-3994'

RECEIVED
 MAR 18 2009
 KCC WICHITA