

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

RECEIVED

Form CP-1
September 2003

WELL PLUGGING APPLICATION

MAR 19 2009

This Form must be Typed
Form must be Signed
All blanks must be Filled

Please TYPE Form and File ONE Copy

KCC DODGE CITY

API # 15-055-21,467-0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

Indicate original spud or completion date (spud) 01/11/96

Well Operator: MAREXCO, Inc. (Owner / Company Name) KCC License #: 9152 (Operator's)

Address: 3033 NW 63rd St. - Suite 151 City: Oklahoma City, OK 73116

State: OK Zip Code: 73116 Contact Phone: (405) 286-5657

Lease: Tancayo Well #: 1-10 Sec. 10 Twp. 25 S. R. 31 East West

N/2 - NE - NW - SE/4 Spot Location / QQQQ County: Finney

2,500 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

1,600 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: none Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 335' Cemented with: 230 Sacks

Production Casing Size: 4 1/2" Set at: 2,631' Cemented with: 575 Sacks

List (ALL) Perforations and Bridgeplug Sets: perforations; 2,587-2,597' - 4 shots/foot

Elevation: 2,784' G.L. / K.B. T.D.: 2,635' P.B.T.D.: 2,631' Anhydrite Depth: 1,824'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole stopped producing economically

Proposed Method of Plugging (attach a separate page if additional space is needed): as per Steve Durrant; dig out cellar, pill spacer, 200# cotton seed hulls, 25 sx cement, gell spacer up to 1,050', fill w/ 225 sx cement to surface, check annulus

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? logs already on file

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 23 2009

CONSERVATION DIVISION
WICHITA, KS

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Stephen W. Marden

Phone: (405) 286-5657

Address: 3033 NW 63rd St. - suite 151 City / State: Oklahoma City, OK 73116

Plugging Contractor: Allied Cementing KCC License #: 99996
(Company Name) (Contractor's)

Address: P.O. Box 31 - Russell, KS 67665 Phone: (785) 483-2627

Proposed Date and Hour of Plugging (if known?): asap

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 03/16/09 Authorized Operator / Agent: MAREXCO, Inc. by Stephen W. Marden
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Handwritten: DUST
RET

Handwritten: KCC PER NE
per
spot
research



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

MAREXCO, INC.
3033 NW 63RD ST - STE 151
OKLAHOMA CITY, OK 73116

March 26, 2009

Re: TANCAYO #1-10
API 15-055-21467-00-00
10-25S-31W, 2500 FSL 1600 FEL
FINNEY COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after September 22, 2009. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888