

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 015-22393 - 00 - 00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date _____

Well Operator: Hawkins Oil LLC KCC License #: 32693
(Owner / Company Name) (Operator's)

Address: 427 S. Boston Ave. Suite #915 City: Tulsa

State: OK Zip Code: 74103 Contact Phone: (918) 382 - 7743

Lease: Marsh A KCCPLT Well #: 11 Sec. 6 Twp. 26 S. R. 5 East West

SE/4 - SE/4 - NE/4 Spot Location / QQQQ County: Butler

2310 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

330 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 225' Cemented with: 175 Sacks

Production Casing Size: 4 1/2" Set at: 2519' Cemented with: 125 Sacks

List (ALL) Perforations and Bridgeplug Sets: Old perms that were squeezed from 2445' - 2452'. New (as of this month) existing perms from 2458' - 2464'

Elevation: 1387 (G.L. / K.B.) T.D.: 2520' PBDT: 2505' Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Set cement plug over Arbuckle perms & tag to ensure it's 50' above zone Tag & pressure test casing. Shoot holes @ 250' & circulate cement to surface.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? Lost our copies...

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 23 2009
CONSERVATION DIVISION
WICHITA, KS

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Ralph Baker

Phone: (316) 322 - 3506

Address: 427 S. Boston Ave. Suite #915 City / State: Tulsa, OK

Plugging Contractor: Phillips Well Service. KCC License #: 5870 KCCPLT
(Company Name) (Contractor's)

Address: PO BOX 1263 Phone: (316) 323 - 2160

Proposed Date and Hour of Plugging (if known?): Roughly March 25th, 2009. Waiting for Application OK & Terry to have a rig free when it's approved

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 3/19/09 Authorized Operator / Agent: _____
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Dist 2
PKT



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

HAWKINS OIL, LLC
427 S BOSTON AVE STE 915
TULSA, OK 74103-4114

March 26, 2009

Re: MARSH A #11
API 15-015-22393-00-00
6-26S-5E, 2970 FSL 330 FEL
BUTLER COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after September 22, 2009. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #2
3450 N. Rock Road, Suite 601
Wichita, KS 67226
(316) 630-4000