

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15-075-20640-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 9-6-97

Well Operator: W.R. Williams, Inc. KCC License #: 32920
(Owner / Company Name) (Operator's)

Address: P.O. Box 15163 City: Amarillo

State: Texas Zip Code: 79105 Contact Phone: (806) 374-4555

Lease: Stanco Well #: 1-27 Sec. 27 Twp. 21 S. R. 40 East West

C - SE - Spot Location / QQQQ County: Hamilton

1320 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

1320 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8-5/8 Set at: 256 Cemented with: 165 Sacks

Production Casing Size: 4-1/2 Set at: 2897 Cemented with: 520 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perf 2822-30, 2833-36, 2842-47, 2860-66, Squeezed with 250 sacks cement with cement retainer @ 2816'. Perf 2784-94.

Elevation: 3532 (G.L. / K.B.) T.D.: 2900 P.B.T.D.: 2880 Anhydrite Depth: Base 2359'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Pump 3 sacks hulls and 15 sacks cement, displace with fresh water, perf 4 holes @ 685', pump 155 sacks cement and circulate to surface.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Dave Olson

Olson Well Service, Inc. Phone: (620) 376-4400, 620-376-8190

Address: 712 3rd Street City / State: Tribune, KS 67879

Plugging Contractor: Allied Cementing Company, Inc. KCC License #: N/A 99996

Address: P.O. Box 31, Russell, KS 67665-0031 Phone: (785) 483-2627

Proposed Date and Hour of Plugging (if known?): October 1, 2004

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: July 27, 2004 Authorized Operator / Agent: W.R. Williams President
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

10/04

RECEIVED
JUL 29 2004
KCC WICHITA

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

W. R. Williams, Inc.
PO Box 15163
Amarillo, TX 79105

August 03, 2004

Re: STANCO #1-27
API 15-075-20640-00-00
SE 27-21S-40W, 1320 FSL 1320 FEL
HAMILTON COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.


Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888

Sincerely



David P. Williams
Production Supervisor