

RECEIVED
NOV 15 2004
KCC WICHITA

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 081-20379 - 00 - 00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 09/17/85

Well Operator: WESTPORT OIL & GAS COMPANY, LP KCC License #: 33002
(Owner / Company Name) (Operator's)

Address: 5735 PINELAND, SUITE 300 City: DALLAS

State: TEXAS Zip Code: 75231 Contact Phone: (214) 692 - 1800

Lease: WAYNE LUCAS Well #: 4 Sec. 21 Twp. 28 S. R. 34 East West

- C - NW - NE Spot Location / QQQQ County: HASKELL

4620 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

1980 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 9-5/8" Set at: 1897' Cemented with: 710 Sacks

Production Casing Size: 5-1/2" Set at: 5633' Cemented with: 635 Sacks

List (ALL) Perforations and Bridgeplug Sets: 5326'-34' - CIBP@5250' W/2SXS; 4863'-??' - CIBP@4800'W/2SXS; 4722'-??' - CIBP @ 4690' W/2SXS.; 4618'-4622' - CIBP@4575'W/2SXS.; 4375'-4387' - OPEN

Elevation: 3032' (G.L. / K.B.) T.D.: 5634' PBDT: 4560' Anhydrite Depth: N/A
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): SET CIBP@4300'W/2 SXS.CMT.; CIRC.WELL W/PXA MUD; CUT&PULL 5-1/2" CSG.@1950'; PUMP 60 SX. CMT. PLUG@1950'-1845' - WOC & TAG; PUMP 50 SX.CMT.PLUG@750'-650'; SPOT 5 SX.CMT.SURF.PLUG@ 13'-3'; DIG OUT & CUT OFF WELLHEAD 3' B.G.L.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: DAVID A. EYLER

Phone: (432) 687 - 3033

Address: 223 W. WALL AVE., SUITE 707 City / State: MIDLAND, TEXAS 79701

Plugging Contractor: NOT YET DETERMINED KCC License #: _____
(Company Name) (Contractor's)

Address: _____ Phone: () _____

Proposed Date and Hour of Plugging (if known?): ESTIMATED 12/01/04

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent
Date: 11/10/04 Authorized Operator / Agent: David A. Eyer
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202