

ORIGINAL

Form ACO-1
September 1999
Form must be Typed

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL COMPLETION FORM *resubmitted w/ additional perms

*Ken
m
3/25/09*

WELL HISTORY - DESCRIPTION OF WELL & LEASE

Operator: License # 32309

Name: Presco Western, LLC

Address 5665 FLATIRON PARKWAY

City/State/Zip BOULDER CO 80301

Purchaser: High Sierra Crude (oil)/BP (gas)

Operator Contact Person: Randy M. Verret

Phone (303) 305-1163

Contractor: Name: Trinidad Drilling

License: 33784

Wellsite Geologist: not applicable

Designate Type of Completion

New Well Re-Entry Workover

Oil SWD SLOW Temp. Abd.

Gas ENHR SIGW

Dry Other (Core, WSW, Expl., Cathodic, etc.)

If Workover/Reentry: Old Well Info as follows:

Operator: _____

Well Name: _____

Original Comp. Date _____ Original Total Depth _____

Deepening Re-perf. Conv. to Enhr./SWD

Plug Back _____ Plug Back Total Depth _____

Commingled _____ Docket No. _____

Dual Completion _____ Docket No. _____

Other (SWD or Enhr?) _____ Docket No. _____

8/02/2007 8/09/2007 3/11/2009

Spud Date or _____ Date Reached TD _____ Completion Date or _____
Recompletion Date _____ Recompletion Date _____

API NO. 15- 081-21724-0000 0001

County Haskell

SW - SE - NE - SE Sec. 30 Twp. 30 S. R. 33 E W

1,614 Feet from SIN (circle one) Line of Section

599 Feet from EW (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:

(circle one) NE SE NW SW

Lease Name SWLVLU Well # 9

Field Name Victory

Producing Formation Lansing

Elevation: Ground 2,949' Kelley Bushing 2,961'

Total Depth 4,400' Plug Back Total Depth _____

Amount of Surface Pipe Set and Cemented at 1,748 Feet

Multiple Stage Cementing Collar Used? Yes No

If yes, show depth set 3,271 Feet

If Alternate II completion, cement circulated from _____

feet depth to _____ w/ _____ sx cmt.

Drilling Fluid Management Plan W0-DG-4/15/09
(Data must be collected from the Reserve Pit)

Chloride content 2,800 ppm Fluid volume 1,100 bbls

Dewatering method used Air Evaporation

Location of fluid disposal if hauled offsite: _____

Operator Name _____

Lease Name _____ License No. _____

Quarter _____ Sec. _____ Twp. _____ S. R. _____ E W

County _____ Docket No. _____

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information on side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.


Signature [Signature]

Title Regulatory Assistant

Subscribed and sworn to before me this 23rd day of March
20 00

Notary Public [Signature]

Date Commission Expires 2-12-2011 My Commission Expires 02/12/2011



KCC Office Use ONLY
 Letter of Confidentiality Attached
If Denied, Yes Date: _____
 Wireline Log Received
 Geologist Report Received
 UIC Distribution (RS 8/27)

JAN 19 1980

Side Two

Operator Name Presco Western, LLC

Lease Name SWLVLU

Well # 9

Sec. 30 Twp. 30 S.R. 33 East West

County Haskell

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken (Attach Additional Sheets.) Yes No

Samples Sent to Geological Survey Yes No

Cores Taken Yes No

Electric Log Run (Submit Copy.) Yes No

List All E.Logs Run:

Cased Hole Compensated Neutron Gamma Ray/CCL Log.
Cement Bond Log

Log Formation (Top), Depth and Datums Sample

Name	Top	Datum
Heebner	4,008'	1,047'
Lansing	4,106'	1,145'

CASING RECORD New Used

Report all strings set-conductor, surface, intermediate, production, etc.

Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs./Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	11"	7"		1,753'	65/35	550	3%cc/1/4 Flo Seal
DV tool	6 1/4"	4 1/2"		4,400'	lite	350	1/4 Flo Seal
Production	6 1/4"	4 1/2"		4,400'	ASC/lite	50/50	2%gel/10%salt

ADDITIONAL CEMENTING/SQUEEZE RECORD

Purpose	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate				
<input type="checkbox"/> Protect Casing				
<input type="checkbox"/> Plug Back TD				
<input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
4	4,106 - 4,114' (Lansing)	24 bbls acid/ 30 bbls flush	
4	4,122 - 4,132' (Lansing)	24 bbls acid/ 30 bbls flush	
4	4,142 - 4,160' (Lansing)	48 bbls acid/ 18 bbls flush	

TUBING RECORD	Size	Set At	Packer At	Liner Run
	2-3/8"	4,170'	4,118'	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No

Date of First, Resumed Production, SWD or Enhr. _____ Producing Method: Flowing Pumping Gas Lift Other (Explain)

Recompletion - added new perfs

Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio	Gravity
	n/a				

Disposition of Gas: Vented Sold Used on Lease Open Hole Perforation Dually Comp. Commingled _____

(If vented, submit ACO-18.) Other (Specify) _____

ALLIED CEMENTING CO., INC.

31084

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Medicine Lodge, KS

DATE 8-4-07	SEC 30	TWP 30S	RANGE 33W	CALLED OUT 5:00pm	ON LOCATION 10:00pm	JOB START 1:00pm	JOB FINISH 2:30pm
LEASE SWLVLU	WELL # 23	LOCATION Satanta KS 1 1/2 S 1 E			COUNTY Haskell	STATE KS	
OLD OR NEW (Circle one)				3 1/2 S into			

CONTRACTOR **Extreme 1** OWNER **Presco-western**

TYPE OF JOB **Surface** CEMENT

HOLE SIZE **11 inch** T.D. **1750** AMOUNT ORDERED **550sx 65:35:16+3%**

CASING SIZE **7 inch** DEPTH **1753** **CC + 2# Flo Seal**

TUBING SIZE DEPTH **150SX class C + 3% CC**

DRILL PIPE DEPTH COMMON **150 C @ 15.40 2310.00**

TOOL DEPTH POZMIX @

PRES. MAX **1100** MINIMUM GEL @

MEAS. LINE SHOE JOINT **22.29** CHLORIDE **23 @ 46.60 1071.80**

CEMENT LEFT IN CSG. **22** ASC @

PERFS. **ALW 550 @ 11.85 6517.50**

DISPLACEMENT **72 Bbls Fresh H2O** **Flo Seal 138 @ 2.00 276.00**

EQUIPMENT HANDLING **758 @ 1.90 1440.20**

MILEAGE **30 x 758 x .09 2046.60**

TOTAL **13662.10**

REMARKS: **Pipe on Bottom, Break Circ, Pump Preflush, Mix 550sx Lit. weight Cement, Mix 150sx tail Cement, Stop Pump, Release Plug, Start Disp, Wash up on Plug, See Steady increase in PSI, Slow Rate, Pump Plug at 12 Bbls total Fresh H2O Disp, Release PSI, Float D.I.H. Hold, Cement P.I. Circ.**

SERVICE DEPTH OF JOB **1753**

PUMP TRUCK CHARGE **1610.00**

EXTRA FOOTAGE @

MILEAGE **30 @ 6.00 180.00**

MANIFOLD **Hedo Rental @ 100.00 100.00**

8 Hrs Wait Time @ 200.00 1600.00

TOTAL **3490.00**

PLUG & FLOAT EQUIPMENT

1-4 1/2 Flex latch down Plug - 360.00

1- Guide Shoe @ 175.00 175.00

1- Sue seal Collar @ 625.00 625.00

1- Basket @ 180.00 180.00

10- centralizer @ 54.00 540.00

2- thread Lark @ 30.00 60.00

1- TRP @ 68.00 68.00

TOTAL **2008.00**

ANY APPLICABLE TAX WILL BE CHARGED UPON INVOICING

TOTAL CHARGE **[scribble]**

DISCOUNT **[scribble]** IF PAID IN 30 DAYS

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 25 2009 CHARGE TO: **Presco-Western**

STREET
CITY STATE ZIP
WICHITA, KS
SWLVLU I
AFE # 07086 KS
8000.160

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE **[Signature]**

PRINTED NAME

ALLIED CEMENTING CO., INC.

28634

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Oakley

DATE <u>8-8-07</u>	SEC <u>30</u>	TWP <u>30N</u>	RANGE <u>33W</u>	CALLED OUT	ON LOCATION <u>9:00am</u>	JOB START <u>10:30am</u>	JOB FINISH <u>12:00pm</u>
LEASE <u>SWLVLU</u>	WELL# <u>9</u>	<u>723</u>	LOCATION <u>Satanta 1 1/2 S 1 E 3/4 S Winto</u>			COUNTY <u>Haskell</u>	STATE <u>KS</u>
OLD OR <input checked="" type="radio"/> NEW (Circle one)							

CONTRACTOR Xtreme Drilling Rig #4

TYPE OF JOB Production (TOP stage)

HOLE SIZE 6 1/4 T.D. 4400'

CASING SIZE 4 1/2" DEPTH 4402'

TUBING SIZE DEPTH

DRILL PIPE DEPTH

TOOL DV DEPTH 3273

PRES. MAX MINIMUM

MEAS. LINE SHOE JOINT 40 1/4'

CEMENT LEFT IN CSG. 40.19

PERFS.

DISPLACEMENT 50 BBL

EQUIPMENT

OWNER same

CEMENT

AMOUNT ORDERED 350 sks Lite

Kit # Flo-seal

COMMON @

POZMIX @

GEL @

CHLORIDE @

ASC @

Lite 350 sks @ 11.25 3937.50

Flo-seal 87# @ 2.00 174.00

HANDLING 377 sks @ 1.90 716.30

MILEAGE 90 sk/mile 182.55

TOTAL 6015.35

PUMP TRUCK CEMENTER Andrew

423-281 HELPER Alan

BULK TRUCK

373 DRIVER Darrin

BULK TRUCK

394 DRIVER Alvin

REMARKS:

Mix 350 sks Lite down center
wash pump and line clean replace
plug down. 1000' LIFT pressure
Till 45 DBLS out last circulation
Pressure dropped to 400' plug landed
Tool closed HOB cement did
circulate
thank you

SERVICE

DEPTH OF JOB

PUMP TRUCK CHARGE 955.00

EXTRA FOOTAGE @

MILEAGE 25 miles @ N/C

MANIFOLD @

TOTAL 955.00

CHARGE TO: Presco western

STREET

CITY

AP Approval Stamp - Drilling Well ZIP	
Well Name	STATE <u>SWLVLU723</u>
Company	<u>Presco Western, LLC - 700</u>
Cost Center	<u>KS061182</u> Date
AFE	<u>07086KS (exp 3-01-08)</u>
Approval	
GL Code	<u>(IOC 8000) ICC 8100 / TE 8200 . 160</u>

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE

RECEIVED
KANSAS CORPORATION COMMISSION
PLUG & FLOAT EQUIPMENT

MAR 25 2009

CONSERVATION DIVISION
WICHITA, KS

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

PRINTED NAME _____

ALLIED CEMENTING CO., INC.

28633

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Oakley KS

DATE <u>8-8-09</u>	SEC <u>30</u>	TWP <u>30S</u>	RANGE <u>33W</u>	CALLED OUT	ON LOCATION <u>9:00 P.m</u>	JOB START <u>10:00 AM</u>	JOB FINISH <u>10:30 AM</u>
LEASE <u>SWLVLU</u>	WELL <u>122</u>	LOCATION <u>Santa Rosa</u>	LOCATION <u>1/2 S E 3/4 S W10</u>		COUNTY <u>Haskell</u>	STATE <u>KS</u>	
OLD OR <u>NEW</u> (Circle one)							

CONTRACTOR Xtreme Drilling Rig #1 OWNER Same

TYPE OF JOB Production (Bottom stage)

HOLE SIZE 6 1/4" T.D. 4400'

CASING SIZE 4 1/2" DEPTH 4402'

TUBING SIZE DEPTH

DRILL PIPE DEPTH

TOOL DV DEPTH 3273'

PRE. MAX MINIMUM

MEAS. LINE SHOE JOINT 40.19'

CEMENT LEFT IN CSG. 40.19'

PERFS.

DISPLACEMENT 69.75 BBL

EQUIPMENT 17.71 water
52.04 mud

PUMP TRUCK CEMENTER Andrew

423-281 HELPER Alan

BULK TRUCK

323 DRIVER Oarrin

BULK TRUCK

DRIVER

CEMENT	AMOUNT ORDERED	<u>50 sks Asc 2 1/2 gal 106 salt</u>
		<u>5* Gilsonite 76% CD-31 28% Defoamer</u>
		<u>50 sks Lite 1/4" Flo-seal</u>
COMMON	@	
POZMIX	@	
GEL <u>1 sk</u>	@	<u>16.65 16.65</u>
CHLORIDE	@	
ASC <u>50 sks</u>	@	<u>14.90 745.00</u>
	@	
<u>Lite 50 sks</u>	@	<u>11.25 562.50</u>
	@	
<u>Salt 5 sks</u>	@	<u>19.20 96.00</u>
<u>Gilsonite 250#</u>	@	<u>.70 175.00</u>
<u>CD-31 15#</u>	@	<u>7.50 112.50</u>
<u>Flo-seal 12#</u>	@	<u>2.00 24.00</u>
<u>Defoamer 15#</u>	@	<u>7.20 108.00</u>
HANDLING <u>120 sks</u>	@	<u>1.90 228.00</u>
MILEAGE <u>94 sk/mile</u>	@	<u>378.00</u>
		TOTAL <u>2445.65</u>

REMARKS:

Mix 50 sks Lite followed by 50 sks Asc wash pump and line clean
Displace plug down 1000' lift
Pressure loaded plug 1500'
Plug landed float held
Open DV tool 800'

Thank you

SERVICE

DEPTH OF JOB		
PUMP TRUCK CHARGE		<u>1675.00</u>
EXTRA FOOTAGE	@	
MILEAGE <u>35 miles</u>	@	<u>6.00 210.00</u>
MANIFOLD <u>head rental</u>	@	<u>100.00</u>
	@	
	@	
		TOTAL <u>1985.00</u>

CHARGE TO: Presco western

STREET

CITY

AP Approval Stamp - Drilling Well ZIP			
Well Name	<u>SWLVLU 123</u>		
Company	<u>Presco Western, LLC - 700</u>		
Cost Center	<u>KS081182</u>	Date	
AFE	<u>07086KS (exp 3-01-08)</u>		
Approval			
GL Code	<u>(ICC 8000) ICC 6100 / TE 8200</u>	<u>160</u>	

To Allied Cementing Co., Inc.

You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

4 1/2" PLUG & FLOAT EQUIPMENT

<u>1 Affu float shoe</u>	@	<u>385.00</u>
<u>(Flex) 1 Latch down plug assy</u>	@	<u>360.00</u>
<u>1 DV tool</u>	@	<u>375.00</u>
<u>2 5/8" Hole control</u>	@	<u>215.00</u>
	@	

RECEIVED
KANSAS CORPORATION COMMISSION

TOTAL 4810.00


TAX MAR 2 5 2009

TO CONSERVATION DIVISION

WICHITA, KS

DISCOUNT IF PAID IN 30 DAYS

SIGNATURE



PRINTED NAME