

15-195-21929-00-00

API NUMBER 15-195-21-929-00-00

LEASE NAME McCall

WELL NUMBER A-1

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

2970 Ft. from (S)N Line of Section (circle one)

4950 Ft. from (E)W Line of Section (circle one)

LEASE OPERATOR Jason Oil Co

SPOT LOCATION _____

ADDRESS Box 701

SEC. 11 TWP. 11 S. RGE 23 (E) or (W)

CITY, STATE, ZIP Russell Kans 67665

COUNTY Trego

PHONE#(487) 4201 OPERATORS LICENSE NO. 6622

Date Well Completed 1985

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Plugging Commenced 11-18-98

Date Plugging Completed 11-18-98

The plugging proposal was approved on 8-10-1998 (date)
by Herb Deines (KCC District Agent's Name)

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation(s) LKC Depth to Top 3530 Bottom 3569 T.D. 3995

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
<u>LKC</u>	<u>oil & water</u>	<u>3530</u>	<u>3533</u>	<u>5 1/2</u>	<u>3995</u>	<u>0</u>
	<u>oil & water</u>	<u>3569</u>	<u>70</u>			

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

8 5/8" set at 217' w/140 sxs cement. 5 1/2" casing at 3995' w/175 sxs cement. Alt II circulated 375 sxs cement from 1784' to surface. Perforated at 3530' and 3569'. Tied to 4 1/2" casing and pumped 40 sxs cement with 250# hulls, followed by 19 sxs gel with 250# hulls. Pumped 140 sxs cement to Max. P.S.I. 600#. S.I.P. 600#. Hooked onto annulus and pumped 5 sxs cement to Max. P.S.I. 500# and shut in. Total 185 sxs 60/40 posmix with 10% gel and 500# hulls. Anhydrite at 1717'
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Jason Oil Company

License No. 6622

Address P. O. Box 701, Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Jason Oil Co

STATE OF KANSAS COUNTY OF Russell, ss.

James L. Schoenberger (Employee of Operator or (Operator) of above-described well, being first

duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James L. Schoenberger

(Address) P. O. Box 701, Russell, KS. 67665

SUBSCRIBED AND SWORN TO before me this 28th day of January, 19 99

Notary Public Fred Weigel, Jr.

My Commission Expires: 7-18-2002

RECEIVED
 2-3-1999
 6661-1999
 11 10 12 AM