

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-195-21966-00-00

API NUMBER 15-195-21,966-00-00

LEASE NAME McCall "A"

WELL NUMBER 2

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

3630 Ft. from S Section Line

4465 Ft. from E Section Line

LEASE OPERATOR Presley Petroleum Co., d/b/a Source Petroleum SEC. 11 TWP. 11 RGE. 23 ~~KXXX~~ (W)

ADDRESS 910 Century Plaza Bldg.

COUNTY Trego

PHONE# (316) 262-7397 OPERATORS LICENSE NO. 3667

Date Well Completed 3-14-88

Character of Well D & A

Plugging Commenced 3-14-88

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 3-14-88

The plugging proposal was approved on 3-11-88 (date)

by Ed Schumaker (KCC District Agent's Name).

Is ACO-1 filed? will be by operator If not, Is well log attached? yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3972

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

Plug #1 set @ 3939' with 20 sacks cement through drill pipe

Plug #2 set @ 1720' with 20 sacks cement through drill pipe

Plug #3 set @ 890' with 100 sacks cement & 1 sack seal flake through drill pipe

Plug #4 set @ 265' with 40 sacks cement through drill pipe (OVER)

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Lobo Drilling Company License No. 5864

Address PO Box 877, Great Bend, KS 67530

STATE OF KANSAS COUNTY OF BARTON, ss.


Ervin Neighbors (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ervin Neighbors

(Address) PO Box 877, Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this RECEIVED day of March, 19 88

STATE CORPORATION COMMISSION  
Deborah M. Hogue  
Notary Public



Expires: \_\_\_\_\_

MAR 16 1988  
3-16-1988

CONSERVATION DIVISION  
Wichita, Kansas

Plug #5 set @ 40' with 10 sacks cement; 15 sacks in rat hole

15-195-21966-00-00

DRILLER'S WELL LOG

DATE COMMENCED: March 7, 1988  
DATE COMPLETED: March 14, 1988

Presley Petroleum Co., d/b/a  
Source Petroleum  
McCall "A" #2  
175' W approx. C, NE SW NW  
Sec. 11-11-23W  
Trego County, KS

0 - 317' surface soil, sand, shale  
317 - 728' shale, red bed  
728 - 1180' sand, shale  
1180 - 1455' sand with sandstone  
1455 - 1575' shale with limestone  
1575 - 1714' shale & red bed  
1714 - 1757' Andydrite  
1757 - 2256' shale, lime  
2256 - 3107' lime, shale  
3107 - 3515' lime, shale  
3515 - 3545' lime  
3545 - 3602' lime, shale  
3602 - 3691' lime  
3691 - 3715' lime, shale  
3715 - 3972' lime  
3972' RTD

ELEVATION: 2236' GL

Surface Pipe: Set used  
8-5/8" @ 217' with 150  
sacks 60/40 pozmix, 2%  
gel, 3% c.c.

A F F I D A V I T

STATE OF KANSAS  
COUNTY OF BARTON) ss

ERVIN NEIGHBORS of lawful age, does swear and state that the facts  
and statements herein are true and correct to the best of his knowledge.

*Ervin Neighbors*  
Ervin Neighbors

SUBSCRIBED AND SWORN to before me this 15 day of March, 1988.



RECEIVED  
STATE CORPORATION COMMISSION  
3-16-1988  
MAR 16 1988

*Dorothy M. Hague*  
Notary Public

CONSERVATION DIVISION  
Wichita, Kansas