

15-195-20138-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Trego County, Sec. 13 Twp. 11 Rge. (E) 23 (W)
C SW SW

NORTH



Locate well correctly on above Section Plat

Location as "NE/CNWxSWx" or footage from lines
Lease Owner Okmar Oil Company
Lease Name Carpenter Well No. 2
Office Address 1130 Wichita Plaza - Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry
Date well completed 10-2 19 69
Application for plugging filed 10-2 19 69
Application for plugging approved 10-2 19 69
Plugging commenced 7:45 AM 10-2 19 69
Plugging completed 11:45 AM 1:30 PM 10-2 19 69
Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3794 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS			CASING RECORD			
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand & Shale		0	230	8 5/8	230	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged hole - drill pipe to 825' Cement w/100 sx 245' w/20 sx
10 sx @ 40' 2 sx in rat hole by Halliburton & Bill Nichols

RECEIVED
STATE CORPORATION COMMISSION
OCT 7 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor B & B Drilling, Inc.
Address 207 Petroleum Building - Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Bill Lahar (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill Lahar
207 Petroleum Building - Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of October, 19 69

My commission expires May 31, 1970
Alma A. Neises
Notary Public.

15-195-20138-00-00

B & B DRILLING, INC.

548 Petroleum Building

Wichita, Kansas 67202

October 6, 1969

DRILLERS LOG

Re: Carpenter #2
C SW SW Section 13-11S-23W
Trego County, Kansas

OPERATOR: Okmar Oil Company
CONTRACTOR: B & B Drilling, Inc.
COMMENCED: September 24, 1969
COMPLETED: October 2, 1969
TOTAL DEPTH: 3794'

0	231	Sand & Shale
231	265	Shale
265	740	Shale & Sand
740	771	Shale
771	864	Sand
864	1549	Shale & Red Bed
1549	1756	Shale & Shells
1756	1813	Anhydrite
1813	1900	Shale & Shells
1900	2250	Sand & Shale
2250	2460	Shale & Shells
2460	2655	Shale & Shells
2655	2785	Lime & Shale
2785	2999	Shale w/ lime
2999	3100	Lime & Shale
3100	3262	Lime & Shale
3262	3400	Lime & Shale
3400	3519	Lime w/shale Strks
3519	3522	Heebner
3522	3563	Lime
3563	3605	Lime
3605	3620	
3620	3650	Lime
3650		
3650	3704	Lime & Shale
3704	3787	Lime
3787	3794	Total Depth

RECEIVED
STATE CORPORATION COMMISSION
OCT 7 1969
CONSERVATION DIVISION
Wichita, Kansas

DST #1
DST #2
DST #3

DST #4

D & A

We certify the above and foregoing to be true and correct copy of the log on the #2 Carpenter, located in Trego County, Kansas

Bill Bahar President

Alma A. Kiser Notary Public
Subscribed and sworn to before me this 6th day of October, My Commission expires May 31, 1970
1969