

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Herman Loeb
Address: PO Box 838, Lawrenceville, ILL 62439
Phone: (618) 943-2227 Operator License #: 3273
Type of Well: oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 03/01/09 (Date)
by: Darrel Dipman (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
morrow Depth to Top: 5120 Bottom: 5129 T.D. 5300
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-199-20119-00-00
Lease Name: Kraut Krammer
Well Number: 1-30
Spot Location (QQQQ): _____ - NE - NE - SE
2310 Feet from North / South Section Line
330 Feet from East / West Section Line
Sec. 30 Twp. 15 S. R. 42 East West
County: Wallace
Date Well Completed: 10/24/1987
Plugging Commenced: 3/2/09
Plugging Completed: 3/2/09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
morrow	oil	424	surface	8 5/8		none
		5258	surface	5 1/2		none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Tubing standing in hole, run tubing in to 2960', connected to tubing, pumped 200 sx cement mixed w/3 sxs cc & 600# hulls, pulled tubing to 2000' pumped 200 sxs cement mixed w/200# hulls, cement to surface, pulled tubing to surface, connected to 8 5/8 surface casing pumped 25 sxs cement max psi 500# to sip 450# connected back to 5 1/2 production casing pumped 50 more sxs max psi 500# - sip 0#

Name of Plugging Contractor: Eastern Colorado Well Service License #: 32997
Address: Cheyenne Wells, Co 80810
Name of Party Responsible for Plugging Fees: Herman Loeb
State of ILL County, _____, ss.

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 23 2009
CONSERVATION DIVISION
WICHITA, KS

Shane Pelton (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) _____

(Address) Box 742 44421 Co Rd Q Cheyenne Wells Colo

SUBSCRIBED and SWORN TO before me this 18th day of March, 2009

Ray Day My Commission Expires: 8-10-2011

Notary Public
43079 Co Rd 93
Cheyenne Wells Co 80810

Mail to: KCC Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten initials]