

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Herman Loeb

Address: PO Box 838, Lawrenceville, ILL 62439

Phone: (618) 943-2227 Operator License #: 3273

Type of Well: oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 3/11/09 (Date)

by: Ken Jehlik (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

morrow Depth to Top: 5164 Bottom: 5180 T.D. 5320

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-071-20188-0002

Lease Name: Edsall E KCCPT Per CP 2/3

Well Number: E-3

Spot Location (QQQQ): _____ - NW - SE - NE *Per GPS KCC ACT*
1980 Feet from North / South Section Line

660 Feet from East / West Section Line

Sec. 11 Twp. 16 S. R. 43 East West

County: Greeley

Date Well Completed: 1/23/1980

Plugging Commenced: 3/10/09

Plugging Completed: 3/11/09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
<u>morrow</u>		<u>469</u>	<u>surface</u>	<u>8 5/8</u>	<u>469</u>	<u>none</u>
		<u>5317</u>	<u>surface</u>	<u>5 1/2</u>	<u>5317</u>	<u>none</u>

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP w/ 2sx cmt @ 5100, test casing to 800 psi, held, perforate 3 shuts @ 1250, run tubing into 2862, spot 25 sxs c/o 2862 to 2812 thru tubing
Pulled out 27 joints tubing, spot 25 sx c/o 2022 to 1772 thru tubing, trip tubing out hooked on to casing, pump 80 sx & 150# hulls, then 145 sc down
5 1/2 casing thru perfs, c/o 1250 down casing psi 300# up to 800# si @ 300#, pump 125 sx down annulus @ 200#, si @ 50# 60/40 poz 4% gel

Name of Plugging Contractor: Shane Pelton Allied Cement Co License #: 99996 *KCCPT*
Address: PO Box 792, Cheyenne Wells, Co 80810

Name of Party Responsible for Plugging Fees: Herman Loeb

State of ILL County, _____, ss.

Shane Pelton (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) Box 792 Hwy 81 Cor. Q Cheyenne Wells Co 80810

SUBSCRIBED and SWORN TO before me this 18th day of March, 2009

[Signature] My Commission Expires: 8-10-2011
Notary Public

43579 Co Rd 95
Cheyenne Wells Co 80810
Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 23 2009
CONSERVATION DIVISION
WICHITA, KS

PKT