

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Downing-Nelson Oil Co., Inc.
Address: P. O. Box 372 Hays, Kansas
Phone: (785) 621-2610 Operator License #: 30717
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 3-02-09 (Date)
by: Case Morris (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Sand Depth to Top: 4034 Bottom: 4038 T.D. 4147
L-KC Depth to Top: 3714 Bottom: 3717 T.D. 4147
Depth to Top: _____ Bottom: _____ T.D. _____

195
API Number: 15-10-22,286-0000
Lease Name: Werth
Well Number: 1-32
Spot Location (QQQQ): _____ - W/2 - E/2 - SW
1330 Feet from North / South Section Line
1700 Feet from East / West Section Line
Sec. 32 Twp. 13 S. R. 21 East West
County: Trego
Date Well Completed: 7-15-05
Plugging Commenced: 3-20-09
Plugging Completed: 3-20-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Sand	Oil and water	4034'	4037'	8 5/8"	222'	None
L-KC	" "	3714'	3717'	5 1/2"	4165'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Tied to 8 5/8" Casing- Mixed 2 sx. 60/40 Poz, 4% Gel and pressured to 200#. SIP-200#. Hooked to 5 1/2" Casing and mixed 50 sx. 60/40 Poz with 200# Hulls. Followed with 12 sxs. Gel. Followed with 200 sx. 60/40 Poz, 4% Gel. Pump pressure about half way in at 700# down to 450# when Cement hit bottom. Went to 1000# and SIP- 1000#. Job complete.


Name of Plugging Contractor: Allied Cementing and Acidizing, Inc. License #: 99990
Address: Russell, Kansas

Name of Party Responsible for Plugging Fees: Downing- Nelson Oil Co. Inc.
State of Kansas County, Ellis, ss.

Terry W. Piesker (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Terry W. Piesker
(Address) _____

SUBSCRIBED and SWORN TO before me this 20th day of March, 2009
Patricia Dreiling My Commission Expires: _____
Notary Public



RECEIVED
KANSAS CORPORATION COMMISSION
99990
MAR 23 2009
CONSERVATION DIVISION
WICHITA, KS

PKT