

15-195-21763-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-195-21,763-00-00

LEASE NAME Walker "A"

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

1320 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 18 TWP. 11 RGE. 23 (E) or (W)

COUNTY Trego

LEASE OPERATOR Raymond Oil Company, Inc.

ADDRESS One Main Place, #900 Wichita, KS 67202

PHONE# (316) 267-4214 OPERATORS LICENSE NO. 5064

Date Well Completed 9-14-85

Character of Well D&A

Plugging Commenced 9-14-85

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 9-14-85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Hays, KS.
to be filed by

Is ACO-1 filed? operator If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4115

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Bottom Plug: @ 1940' w/25 sacks 60/40 pozmix 6% gel thru drill pipe
Next Plug: @ 1000' w/100 " " " " " " & 1 sack Floscele
Next Plug: @ 240' w/40 sacks " " " " " " "
Top Plug: @ 40' w/solid bridge of 1 sack hulls & 10 sacks cement (10 sacks in Rat Hole)
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address P.O. Box 823 Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.

Bill Draney (Employee of Operator) or ~~Operator~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Bill Draney

(Address) Box 823 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 18 day of Sept, 1985

Dorothy M. Idague
Notary Public

My Commission Expires: 4-29-86

RECEIVED
STATE CORPORATION COMMISSION

SEP 20 1985
9-20-1985
CONSERVATION DIVISION
Wichita, Kansas

15-195-21763-00-00

DRILLER'S WELL LOG

DATE COMMENCED: September 7, 1985
DATE COMPLETED: September 14, 1985

Raymond Oil Company, Inc.
WALKER "A" #1
C - SE/4
Sec. 18, T11S, R23W
Trego County, Ks.

ELEVATION: 2359' K.B.

0 - 1918' Surface Soil, Shale, Sand
1918 - 1965' Anhydrite
1965 - 3452' Lime & Shale
3452 - 3678' Lime
3678 - 3712' Shale & Lime
3712 - 3951' Lime
3951 - 4076' Shale
4076 - 4115' Lime, Shale, Chert
4115' RTD

FORMATION DATA

Anhydrite	1918'
Topoka	3452'
Seebner	3678'
Lansing	3713'
Base K.C.	3951'
Marathon	4076'
RTD	4115'

Surface Pipe: Set used
6-5/8", 24# @215' w/150
Sacks 60/40 pozmix 28 gal
38 cc.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

Bill Draney of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Bill Draney

Subscribed and sworn to before me this 18 day of September 1985.

My Comm. Expires:

4-29-86

Dorothy M. Dague
Notary Public

RECEIVED
STATE COMPTROLLER COMMISSION
9-20-1985
SEP 20 1985

CONSERVATION DIVISION
Wichita, Kansas