


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Trego County, Sec. 26 Twp. 11 Rge. 23 (E) W (W)

Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines NE SW NW
Lease Owner B & R Drilling, Inc.
Lease Name Howatt Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 11-3-51 19
Application for plugging filed 12-8-51 19
Application for plugging approved 12-8-51 19
Plugging commenced 12-8-51 19
Plugging completed 1-10-52 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3752 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	181	None
				5 1/2	3752	1089

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugging Record

Plugged back with crushed rock to 3630', dumped 4 sax cement with dump bailer, top of cement 3602'. Mudded hole to 180', set rock bridge, dumped 15 sax cement. Top of cement 130', mudded hole to 35', set rock bridge. Dumped 10 sax cement at 35', for cap.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor
Address

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
W. A. Michaelis, Jr. (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. A. Michaelis, Jr.
Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of January, 1952
Clara Lamm
Notary Public.

My commission expires 6-17-54

PLUGGING
FILE SEC 26 T 11 R 23
BOOK PAGE 132 LINE 1

23-8390-s

6-51-20M

JAN 23 1952

15-195-01487-00-00

B & R Drilling, Inc.
Howat No. 1

NE SW NW Sec. 26-11-23W
Trego County, Kansas

Total Depth: 3752'
Comm: 10-19-51
Comp: 11-3-51

Casing

8 5/8" Set @ 181'
5 1/2" Set @ 3752'

Cement

125 sacks of Lone Star
100 sacks of Lone Star

Formation

Depth

Surface soil-sand-clay	40
Clay	50
Clay-shale	181
Shale-shells	500
Shale-sand-shells	895
Sand----	900
Sand-Hard	940
Sand	1010
Shale-sand	1260
Sand-shele--shells	1535
Sand-shale	1615
Shale-Redrock	1852
Shale-shells	1878
Shale	2040
Shale-lime	2210
Shale	2380
Lime-shale	2450
Lime	2500
Shale	2595
Lime-Shale	2745
Shale-little lime	2870
Lime-shale	3122
Lime	3190
Lime-shale	3680
Lime	3702
Lime-shale	3735
Lime	3752

STATE OF KANSAS)
) ss
RUSSELL COUNTY)

I hereby certify that the above information is true and correct to the best of my knowledge.

-----Cora Bety-----

Subscribed and sworn to before me this ^{22nd} ~~15th~~ day of ^{January} ~~November~~, 1952.

Clay Linn

My commission expires: 6-17-54.

1-23-1952

PLUGGING
FILE SEC 26-11-23W
BOOK PAGE 132 LINE 1