

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Anderson Energy, Inc.
Address: 221 S. Broadway, Suite 312 Wichita, KS 67202
Phone: (316) 263-1006 Operator License #: 6484
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 10/27/2008 (Date)
by: Marvin Miller (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: 3428 Bottom: 3441 T.D. 3441
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-051-05872-00-00
Lease Name: Rumsey
Well Number: 31
Spot Location (QQQQ): SW - NE - NE -
990 Feet from North / South Section Line
990 Feet from East / West Section Line
Sec. 23 Twp. 11 S. R. 17 East West
County: Ellis
Date Well Completed: 1/14/1940
Plugging Commenced: 10/27/2008
Plugging Completed: 10/28/2008

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	Oil & Water	0	135'	12'	135'	0
		0	1140'	8-5/8"	1140	0
		0	3428'	4-1/2"	3428	0

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 08 2009
CONSERVATION DIVISION
WICHITA, KS


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

2-7/8 tubing @ 3030'. Spot 100 sx w/200# hulls, pull tubing to 1500', pump 350 sx w/400# hulls, pull tubing to 1000'. Mix 250 sx w/200# hulls, pull tubing to 650'. Mix 225 sx w/ 500# hulls.

TOOH to tag cement. Tagged solid cement @ 460'. Perforate 2 holes @ 400'. TIH w/ tubing to 375'. Mix 50 sx and circulated cement up 4-1/2" csg. Shut-in 4-1/2" & mix 30 sx and circulate up 8-5/8" csg. TOOH w/ tubing and load 4-1/2" casing w/5 sx.

Name of Plugging Contractor: Express Well Service & Supply, LLC License #: 6426
Address: 1110 Highway 40, Victoria, KS 67671-0019
Name of Party Responsible for Plugging Fees: Anderson Energy, Inc.
State of Kansas County, Sedgwick, ss.
William L. Anderson (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) William L. Anderson

(Address) 221 S. Broadway, #312 Wichita, KS 67202

Subscribed and SWORN TO before me this 6 day of January, 20 09
Glynne Bolte My Commission Expires: 4-24-2011
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Handwritten initials

ALLIED CEMENTING CO., LLC. 32234

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: Russell *well file*

DATE <u>10-28-08</u>	SEC. <u>23</u>	TWP. <u>11</u>	RANGE <u>17</u>	CALLED OUT	ON LOCATION	JOB START <u>3:00 PM</u>	JOB FINISH <u>4:00 PM</u>
LEASE <u>Rumsey</u>		WELL # <u>31</u>		LOCATION <u>Cedell RNgd 15 1 E</u>		COUNTY <u>Ellis</u>	STATE <u>K</u>
<input checked="" type="radio"/> OLD OR NEW (Circle one)							

CONTRACTOR E Express

TYPE OF JOB plug

HOLE SIZE	T.D.
CASING SIZE <u>4 1/2</u>	DEPTH
TUBING SIZE <u>2 3/8</u>	DEPTH
DRILL PIPE	DEPTH
TOOL	DEPTH
PRES. MAX	MINIMUM
MEAS. LINE	SHOE JOINT
CEMENT LEFT IN CSG.	
PERFS.	
DISPLACEMENT	

OWNER _____

CEMENT AMOUNT ORDERED 200 sh 6940-4
Used 85 sh

COMMON	<u>51</u>	@	<u>13.50</u>	<u>688.50</u>
POZMIX	<u>34</u>	@	<u>7.55</u>	<u>256.70</u>
GEL	<u>3</u>	@	<u>20.25</u>	<u>60.75</u>
CHLORIDE		@		
ASC		@		
HANDLING	<u>203</u>	@	<u>2.25</u>	<u>456.75</u>
MILEAGE	<u>5K/mi / .10</u>			<u>507.50</u>
TOTAL				<u>1990.20</u>

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 08 2009
CONSERVATION DIVISION
WICHITA, KS

EQUIPMENT

PUMP TRUCK # <u>409</u>	CEMENTER <u>Bill</u>
	HELPER <u>Craig</u>
BULK TRUCK # <u>481</u>	DRIVER <u>Nest</u>
BULK TRUCK # _____	DRIVER _____

REMARKS:

Tubing 400 mix 50 sh
pipe to surface
closed backside mixed
30 sh cement to surface on backside
of CSG
top off w/ 5 sh

SERVICE

DEPTH OF JOB	
PUMP TRUCK CHARGE	<u>875.00</u>
EXTRA FOOTAGE	@ _____
MILEAGE <u>25</u>	@ <u>7.00</u> <u>175.00</u>
MANIFOLD	@ _____
	@ _____
	@ _____
TOTAL <u>1050.00</u>	

CHARGE TO: Anderson Energy

STREET _____

CITY _____ STATE _____ ZIP _____

To Allied Cementing Co., LLC.
You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME _____

SIGNATURE Terry W. Piesker

SALES TAX (If Any) _____

TOTAL CHARGES _____

DISCOUNT _____ IF PAID IN 30 DAYS

ALLIED CEMENTING CO., LLC. 034930

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: *Well FILE*
Russell KS

DATE <u>10-27-08</u>	SEC. <u>23</u>	TWP. <u>11</u>	RANGE <u>17</u>	CALLED OUT	ON LOCATION	JOB START <u>9:15pm</u>	JOB FINISH <u>10:30pm</u>
LEASE <u>Rumsey</u>		WELL # <u>31</u>		LOCATION <u>Codeil Rd & River Rd Jct. 1 South</u>		COUNTY <u>Ellis</u>	STATE <u>KS</u>
<input checked="" type="radio"/> OLD OR NEW (Circle one)				<u>1 East South into</u>			

CONTRACTOR Express Well Service

TYPE OF JOB Plug Well

HOLE SIZE	T.D.
CASING SIZE <u>4 1/2</u>	DEPTH
TUBING SIZE <u>2 7/8</u>	DEPTH <u>3030'</u>
DRILL PIPE	DEPTH
TOOL	DEPTH
PRES. MAX	MINIMUM
MEAS. LINE	SHOE JOINT
CEMENT LEFT IN CSG.	
PERFS.	
DISPLACEMENT	

OWNER _____

CEMENT 925

AMOUNT ORDERED ~~1350~~ 6940 4% Gel

~~800# Hulls~~ 1300# Hulls

COMMON	<u>555</u>	@ <u>13.50</u>	<u>7492.50</u>
POZMIX	<u>370</u>	@ <u>7.52</u>	<u>2793.50</u>
GEL	<u>32</u>	@ <u>20.25</u>	<u>648.00</u>
CHLORIDE		@	
ASC		@	
<u>Hulls 13</u>		@ <u>31.00</u>	<u>403.00</u>
		@	
		@	
		@	
		@	
		@	
HANDLING	<u>970</u>	@ <u>2.25</u>	<u>2182.50</u>
MILEAGE	<u>57/mi.</u>	@ <u>1.00</u>	<u>57.00</u>
TOTAL			<u>15945.00</u>

EQUIPMENT

PUMP TRUCK	CEMENTER <u>John Roberts</u>
# <u>409</u>	HELPER <u>Travis</u>
BULK TRUCK	
# <u>396</u>	DRIVER <u>Chad</u>
BULK TRUCK	
# <u>410</u>	DRIVER <u>Neal</u>
# <u>481</u>	<u>Robert</u>

REMARKS:

Ran 2 7/8" tubing to 3030' and spot 100sk w/ 200# Hulls. Pulled up to 1500' mixed 350 sk w/ 400# Hulls. Pulled up to 1000' mixed 250 sk cement w/ 200# Hulls. Pulled up to 650' mix 225 sk w/ 500# Hulls. Pulled out of hole and will tag cement the next day.

CHARGE TO: Anderson Energy

STREET _____

CITY _____ STATE _____ ZIP _____

SERVICE

DEPTH OF JOB	
PUMP TRUCK CHARGE	<u>875.00</u>
EXTRA FOOTAGE	@
MILEAGE	<u>25</u> @ <u>7.00</u> <u>175.00</u>
MANIFOLD	@
	@
	@
TOTAL <u>1050.00</u>	

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 08 2009

To Allied Cementing Co., LLC.

You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PLUG & FLOAT EQUIPMENT

	@	
	@	
	@	
	@	
	@	
TOTAL _____		
SALES TAX (If Any)	_____	
TOTAL CHARGES	_____	
DISCOUNT	_____ IF PAID IN 30 DAYS	

PRINTED NAME _____

SIGNATURE Henry W. Piesha