

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 05 2009
CONSERVATION DIVISION
WICHITA, KS

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: H & C Oil Operating, Inc.
Address: P.O. Box 86 Plainville, KS 67663
Phone: (785) 434-7434 Operator License #: 8914
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 12-29-2008 (Date)
by: Richard Williams, Hays Office (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
LKC Depth to Top: 3659 Bottom: 3657 T.D. 3690
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 163-23393-00-00
Lease Name: Kern A
Well Number: 1
Spot Location (QQQQ): SE - SW - SW -
490 Feet from North / South Section Line
1080 Feet from East / West Section Line
Sec. 28 Twp. 9 S. R. 20 East West
County: Rooks
Date Well Completed: 2-2004
Plugging Commenced: 12-29-08
Plugging Completed: 12-29-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
LKC	Oil & water	227	surface	8 5/8"	227'	None
ARB	Oil & water	3914	surface	5 1/2"	3914'	None


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pump down 5 1/2" casing with 50 sacks cement and 200# hulls. Pump 13 sacks gel with 200# hulls as spacer. Mix 165 sacks cement to top off.
Pressure backside to 500#. 60/40 Posmix 4% gel.

Name of Plugging Contractor: Allied Cementing License #: 99996 KCCAS
Address: Russell, Kansas

Name of Party Responsible for Plugging Fees: H & C Oil Operating, Inc.
State of Kansas County, Rooks, ss.

Charles R. Ramsay (President) (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Charles R Ramsay
(Address) P.O. Box 86 Plainville, KS 67663

SUBSCRIBED and SWORN TO before me this 2nd day of January, 2009
Irene Fellhoelter My Commission Expires: 4/4/11
Notary Public

ALLIED CEMENTING CO., LLC. 034989

JAN 05 2009

TO P.O. BOX 31
RUSSELL, KANSAS 67665
CONSERVATION DIVISION
WICHITA, KS

SERVICE POINT:
Russell KS

DATE <u>12-29-08</u>	SEC. <u>28</u>	TWP. <u>9s</u>	RANGE <u>20w</u>	CALLED OUT	ON LOCATION	JOB START <u>11:45pm</u>	JOB FINISH <u>12:00pm</u>
LEASE <u>Kern A</u>	WELL # <u>1</u>	LOCATION <u>Ellis N to booster station 1/4 East</u>			COUNTY <u>Reels</u>	STATE <u>KS</u>	
QED OR NEW (Circle one)			<u>North into</u>				

CONTRACTOR _____
TYPE OF JOB Plug Abandoned Well
HOLE SIZE _____ T.D. _____
CASING SIZE 5 1/2 DEPTH 3690'
TUBING SIZE _____ DEPTH _____
DRILL PIPE _____ DEPTH _____
TOOL _____ DEPTH _____
PRES. MAX _____ MINIMUM _____
MEAS. LINE _____ SHOE JOINT _____
CEMENT LEFT IN CSG. _____
PERFS. 3657'
DISPLACEMENT _____

EQUIPMENT

PUMP TRUCK CEMENTER John Roberts
409 HELPER Travis
BULK TRUCK _____
473 DRIVER Mike
BULK TRUCK _____
_____ DRIVER _____

REMARKS:

Mix 50 sk cement w/ 200 # Hulls
Mix 13 sk Gel spacer w/ 200 # Hulls
Mix 165 sk cement to top off well
Press. backside @ 500 psi

CHARGE TO: H&C Oil
STREET _____
CITY _____ STATE _____ ZIP _____

To Allied Cementing Co., LLC.
You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME _____

SIGNATURE Charles Ramsey

OWNER _____
CEMENT (Used 215 sk cement 400 # Hulls 13 Gel)
AMOUNT ORDERED 300 w/ 40 4 1/2 Gel
500 # Hulls
15 sk Gel on side

COMMON	<u>129</u>	@	<u>13.50</u>	<u>1741.50</u>
POZMIX	<u>86</u>	@	<u>7.55</u>	<u>649.30</u>
GEL	<u>20</u>	@	<u>20.25</u>	<u>405.00</u>
CHLORIDE		@		
ASC		@		
	<u>400 # Cottonseed Hulls</u>	@	<u>31.05</u>	<u>124.20</u>
	<u>4 sk</u>	@		
		@		
		@		
		@		
		@		
HANDLING	<u>215</u>	@	<u>2.25</u>	<u>483.75</u>
MILEAGE	<u>110 sk/mile</u>			<u>860.00</u>
TOTAL				<u>4263.75</u>

SERVICE

DEPTH OF JOB				
PUMP TRUCK CHARGE				<u>875.00</u>
EXTRA FOOTAGE		@		
MILEAGE	<u>40</u>	@	<u>7.00</u>	<u>280.00</u>
MANIFOLD		@		
		@		
		@		
TOTAL				<u>1,155.00</u>

PLUG & FLOAT EQUIPMENT

	@			
	@			
	@			
	@			
	@			
TOTAL				_____

SALES TAX (If Any) _____
TOTAL CHARGES _____
DISCOUNT _____ IF PAID IN 30 DAYS