

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Clipper Energy LLC

Address: 3838 Oak Lawn #1310 Dallas, TX. 75219

Phone: (214) 220-1080 Operator License #: 33979

Type of Well: D&A Oil KCC PKT per CP213 Docket #: na  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 11-24-08 (Date)

by: Pat Bodore (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (If needed attach another sheet)

Lansing/Kansas City Depth to Top: 3160 Bottom: 3367 T.D. 3528

Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-163-23713-00-00

Lease Name: Bobeck

Well Number: 1

Spot Location (QQQQ): se - sw - se - ne

2550 Feet from  North /  South Section Line

700 Feet from  East /  West Section Line

Sec. 7 Twp. 8 S. R. 20  East  West

County: Rooks

Date Well Completed: 5-30-08

Plugging Commenced: 11-24-08

Plugging Completed: 11-24-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		surface	210	8 5/8	210	none
		surface	3526	5 1/2	3526	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

set BP @ 3420, mixed 50 sks with 200# hulls followed by 14 sks gel spacer and top off with 140 sks cement. Check backside and pressured up to 200 psi.

total cement ordered was 200 sks 60/40 4% gel and plugged down casing

Name of Plugging Contractor: Allied Cementing Co, Inc License #: 99996

Address: P.O. Box 31 Russell, KS. 67665

Name of Party Responsible for Plugging Fees: Clipper Energy, LLC

State of Kansas County, Rooks, ss.

Bill Robinson (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) B. O.

(Address) P.O. Box H Plainville, KS. 67663

SUBSCRIBED and SWORN TO before me this 31<sup>st</sup> day of December, 20 08

Sheryln Axelson My Commission Expires: 7-24-12  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas



RECEIVED  
KANSAS CORPORATION COMMISSION  
JAN 02 2009

CONSERVATION DIVISION  
WICHITA, KS

# ALLIED CEMENTING CO., LLC. 034967

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:

Russell KS

DATE <u>11-25-08</u>	SEC. <u>7</u>	TWP. <u>8s</u>	RANGE <u>20w</u>	CALLED OUT	ON LOCATION	JOB START <u>11:00</u>	JOB FINISH <u>11:30</u>
BOBECK LEASE		WELL # <u>1</u>		LOCATION <u>Damar KS 4 1/2 North on black top</u>		COUNTY <u>Rooks</u>	STATE <u>KS</u>
<input checked="" type="radio"/> OLD OR NEW (Circle one)			West into				

**CONTRACTOR**

TYPE OF JOB Plug down casing

HOLE SIZE \_\_\_\_\_ T.D. \_\_\_\_\_

CASING SIZE 5 1/2 14" DEPTH 3420'

TUBING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_

DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_

TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_

PRES. MAX \_\_\_\_\_ MINIMUM \_\_\_\_\_

MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_

CEMENT LEFT IN CSG. \_\_\_\_\_

PERFS. 3160-3367

DISPLACEMENT \_\_\_\_\_

**OWNER**

**CEMENT**

AMOUNT ORDERED 200 60/10 4 1/2 Gel

On side 200# Hulls and 14 sk Gel

COMMON	<u>114</u>	@	<u>13.50</u>	<u>1539.00</u>
POZMIX	<u>76</u>	@	<u>7.50</u>	<u>573.80</u>
GEL	<u>21</u>	@	<u>20.25</u>	<u>425.25</u>
CHLORIDE		@		
ASC		@		
<u>Cottonseed Hulls 200#</u>		@	<u>31.05</u>	<u>124.20</u>
		@		
		@		
		@		
		@		
		@		
		@		
HANDLING	<u>225</u>	@	<u>2.25</u>	<u>506.25</u>
MILEAGE	<u>.104/sk/mile</u>			<u>1237.50</u>
<b>TOTAL</b>				<u>4406.00</u>

**EQUIPMENT**

PUMP TRUCK CEMENTER John Roberts

# 409 HELPER Travis

BULK TRUCK

# 410 DRIVER Neale

BULK TRUCK

# \_\_\_\_\_ DRIVER \_\_\_\_\_

**REMARKS:**

BP@ 3420 Perfs. 3160-3367

Mixed 50sk cement w/ 200# Hulls

followed by 14 sk Gel spacer and

top off w/ 140 sk cement

Check the back side and

pressured up to 200psi.

*Thanks!*

CHARGE TO: Clipper Energy

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

**SERVICE**

DEPTH OF JOB				
PUMP TRUCK CHARGE			<u>875.00</u>	
EXTRA FOOTAGE	@			
MILEAGE	<u>55</u>	@	<u>7.00</u> <u>385.00</u>	
MANIFOLD	@			
	@			
	@			
<b>TOTAL</b>				<u>1260.00</u>

RECEIVED  
KANSAS CORPORATION

JAN 02 2009

CONSERVATION DIVISION  
WICHITA, KS

**PLUG & FLOAT EQUIPMENT**

_____	@		
_____	@		
_____	@		
_____	@		
_____	@		

TOTAL \_\_\_\_\_

SALES TAX (If Any) \_\_\_\_\_

TOTAL CHARGES \_\_\_\_\_

DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

To Allied Cementing Co., LLC.  
You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME \_\_\_\_\_

SIGNATURE 