

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

JAN 07 2009

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: VESS OIL CORPORATION
Address: 1700 Waterfront Parkway, Bldg. 500, Wichita, KS 67206
Phone: (316) 682-1537 Operator License #: 5030
Type of Well: ENHR Docket #: E-15,099
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) *(If SWD or ENHR)*
The plugging proposal was approved on: 12/15/08 (Date)
by: Steve Bond (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
LKC Depth to Top: 3649 Bottom: 3846 T.D. 3907
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-039-00590-0001
Lease Name: Adel NW Unit - nwadell
Well Number: 7W KCC PRT Per CP2/3
Spot Location (QQQQ): _____ - SW - NW - NW
960 Feet from North / South Section Line
241 Feet from East / West Section Line
Sec. 35 Twp. 5 S. R. 27 East West
County: Decatur
Date Well Completed: 4/19/52
Plugging Commenced: 12/18/08
Plugging Completed: 12/18/08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	279	
				5-1/2"	3907	

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

TIH w/ open ended tbg. to 3400' & tagged hard fill up - pulled to 3369' - RU Schippers Oilfield Serv. - mixed & pumped 80 sxs 60/40 common w/4% gel, blended w/600# hulls - pulled to 2500' pmpd 18 sxs. gel spacer -pld to 2240', pmpd 25 sx cmt & hole loaded & circ. @ end of dis. - pld to 1465' - pmpd 100 sx cmt., blended w/ 200# hulls - circ. gel & light cmt. - pulled to 330', pumped 50 sxs. cmt & had good cmt. to sur. - TOH w/ tbg. - tied onto 8-5/8" & pumped 20 sx cmt., press. to 250# & shut in - tied onto 5 1/2" csg. & topped off w/ 10 sxs. - washed up & RDMO - witnessed & approved by Darrel Dipman, State of Kansas

Name of Plugging Contractor: Schippers Oilfield Services, LLC License #: 34115
Address: RR 1, Box 90D, Hoxie, KS 67740

Name of Party Responsible for Plugging Fees: Vess Oil Corporation
State of Kansas County, Sedgwick, ss.

Pat Canaday (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) [Signature]
(Address) 1700 Waterfront Parkway, Bldg. 500, Wichita, KS 67206

SUBSCRIBED and SWORN TO before me this 5th day of January

[Signature]
Notary Public

My Commission Expires:

20 09



PRT

Schippers Oilfield Services LLC
 RR 1 Box 90D
 Hoxie, KS 67740

RECEIVED
 KANSAS CORPORATION COMMISSION

JAN 07 2009

CONSERVATION DIVISION
 WICHITA, KS



DEC 24 2008

Date 12/22/2008
 Invoice # 306

Bill To

Vess Oil Corp.
 1700 N. Waterfront Pkwy, Bldg. 500
 Wichita, KS 67206-6619

Lease/Service

Northwest Adell #7
 Old Hole Plug

Adell #7

Service Date 12/18/2008
 Due Date 1/21/2009
 Terms Net 30

Item	Description	Qty	Price	Amount
cement	common	210	14.50	3,045.00T
Pozmix		140	7.00	980.00T
Gel	Bentonite	30	17.50	525.00T
Hulls	cottonseed	16	26.50	424.00T
handling of materials	per sack	350	1.95	682.50
mileage and labor		25	31.50	787.50
pump truck charge	pumping job		1,075.00	1,075.00
pump truck mileage		25	6.50	162.50T
cement	common - credit for unused cement		-750.00	-750.00T

COPY

TAKE 10% DISCOUNT IF PAID WITHIN 20 DAYS. DEDUCT FROM TOTAL.

Subtotal \$6,931.50
 Sales Tax (6.3%) \$276.35
 Total \$7,207.85
 Payments/Credits \$0.00
 Balance Due \$7,207.85

Schippers Oilfield Services LLC
 sosllc@ruraltel.net
 FAX: 785.675.9938

Cell: 785.675.8974
 Office: 785.675.9991

(720.79)
 6487.06

JAN 07 2009

CONSERVATION DIVISION
WICHITA, KS

BARNETT DRILLING, INC.
LOG OF MARY A. TAYLOR WELL NO. 1
SW $\frac{1}{4}$ NW $\frac{1}{4}$ NW $\frac{1}{4}$ SECTION 35-5S-27W.
DECATUR COUNTY, KANSAS

DATE COMMENCED: April 8, 1952.


DATE COMPLETED: April 19, 1952.

<u>Formation</u>	<u>From</u>	<u>To</u>	<u>Remarks</u>
Clay and Sand	0	40	
Sand	40	60	
Shale and Shells	60	225	
Sand	225	255	
Shale and Shells	255	279	Set 8 5/8" Surface Pipe @ 279 feet; Cemented with 200 sacks.
Shale and Shells	279	1100	
Sand	1100	1300	
Shale	1300	1350	
Shale and Shells	1350	1750	
Lime	1750	1787	
Shale and Shells	1787	2240	
Anhydrite	2240	2277	
Shale	2277	2420	
Shale and Lime	2420	2685	
Lime	2685	2753	
Lime and Shale	2753	2990	
Lime	2990	3037	
Lime and Shale	3037	3170	
Lime	3170	3195	
Shale and Lime	3195	3260	
Lime	3260	3605	
Lime and Shale	3605	3660	
Lime	3660	3910	
Total Depth		3910	

2240
2659
2240
419

Certificate.

I, F. R. Stubblefield, of Barnett Drilling, Inc., hereby certify that to the best of my knowledge and belief, the above is a true and correct log of the Mary A. Taylor Well No. 1, located SW $\frac{1}{4}$ NW $\frac{1}{4}$ NW $\frac{1}{4}$ of Section 35-5S-27W, Decatur County, Kansas.



Subscribed and sworn to before me, in and for the County of Sedgwick, State of Kansas, this 24th day of April, 1952.



Notary Public

My commission expires February 27, 1956.

JAN 07 2009

REMIT TO
RR 1 BOX 90 D
HOXIE KS 67740

SCHIPPERS OIL FIELD SERVICE L.L.C. CONSERVATION DIVISION
WICHITA, KS

306

DATE <i>1/14/09</i>	SEC. <i>5</i>	RANGE/TWP. <i>30 7W</i>	CALLED OUT	ON LOCATION	JOB START	JOB FINISH
LEASE <i>N. 1/4 - P. 1.1</i>			WELL # <i>7</i>			
			EIR			

CONTRACTOR <i>117 Pl.</i>	OWNER <i>1/0</i>		
TYPE OF JOB <i>DRILL</i>			
HOLE SIZE	T.D.	CEMENT	
CASING SIZE <i>5 1/2</i>	DEPTH	AMOUNT ORDERED	
TUBING SIZE <i>3 1/2</i>	DEPTH		
DRILL PIPE	DEPTH		
TOOL	DEPTH		
PRES. MAX	MINIMUM	COMMON	@
DISPLACEMENT	SHOE JOINT	POZMIX	@
CEMENT LEFT IN CSG.	<i>250 lbs</i>	GEL	@
PERFS		CHLORIDE	@
		ASC	@
EQUIPMENT			@
PUMP TRUCK			@
#			@
BULK TRUCK			@
#			@
BULK TRUCK			@
#			@
		HANDLING	@
		MILEAGE	@
		TOTAL	

REMARKS	SERVICE <i>117 Pl.</i>	
<i>3000' 47' 1410' 1611'</i>	DEPT OF JOB	@
<i>2500' 1500'</i>	PUMP TRUCK CHARGE	@ 1075
<i>1405' 500'</i>	EXTRA FOOTAGE	@
<i>300' 50'</i>	MILEAGE <i>70</i>	@ 1400
<i>200' 100'</i>	MANIFOLD	@
<i>200' 100'</i>		@
<i>100' 100'</i>	TOTAL	

CHARGE TO: <i>1/0</i>	
STREET	STATE
CITY	ZIP

To: Schippers Oil Field Service LLC
You are hereby requested to rent cementing equipment and furnish staff to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

PLUG & FLOAT EQUIPMENT	@
<i>unused 6500 credit</i>	@ -750 credit
<i>60/40</i>	@
	@
	@
TOTAL	<i>1000</i>
TAX	
TOTAL CHARGE	
DISCOUNT (IF PAID IN 20 DAYS)	

SIGNATURE *[Handwritten Signature]*

PRINTED NAME