


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Ellis County. Sec. 25 Twp. 11S Rge. 16W (E)\_\_\_\_(W)  
Location as "NE/CNW%SW%" or footage from lines NE NW NW  
Lease Owner Kern Drilling Company, Inc.  
Lease Name Chrisler Well No. 1  
Office Address P. O. Box 688, Magnolia, Arkansas 71753  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed August 25 19 68  
Application for plugging filed August 25 19 68  
Application for plugging approved August 25 19 68  
Plugging commenced August 25 19 68  
Plugging completed August 25 19 68  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Box 582, Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3469 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Casing		0	209'	8 5/8"	209'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plug:

- 450'/70 sacks cement
- 210'/20 sacks cement
- 40'/10 sacks cement

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 30 1968  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Hellar Drilling Company, Inc.  
Address 339 Union Center, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
D. L. Hellar, Pres. of Hellar Drlg. Co. Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature] D. L. Hellar, President  
339 Union Center, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of August, 19 68

[Signature]  
Catherine Darcey Notary Public.



March 25, 1972

DRILLER'S LOG

COMPANY: Kern Drilling Company, Inc., Magnolia, Ark.  
 CONTRACTOR: Hellar Drilling Company, Inc. Wichita, Kans.  
 LEASE: #1 Chrisler  
 LOCATION: NE NW NW Sec. 25-11S-16W, Ellis County, Ks.  
 COMMENCED: August 16, 1968  
 COMPLETED: August 25, 1968  
 CASING: Set 8 5/8" Surface Casing @ 209'/150 sacks cement

0-30	Post Rock
30-215	Post Rock & Shale
215-890	Sand & Shale
890-926	Shale
926-965	Anhydrite
965-1440	Red Bed & Shale
1440-1670	Shale & Red Bed
1670-1775	Lime & Shale (Ft. Riley)
1775-2109	Ft. Riley Lime & Shale
2109-2702	Lime & Shale
2702-2776	Topeka Lime
2776-3434	Lime & Shale
3434-3469	Arbuckle dolomite
3469	Rotary Total Depth

D & A

RECEIVED  
 STATE COMMISSION  
 AUG 30 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

I, D. L. Hellar, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 Chrisler, located in NE NW NW Sec. 25-11S-16W, Ellis County, Kansas, as reflected by the files of the Hellar Drilling Company, Inc.

HELLAR DRILLING COMPANY, INC.

By: *D. L. Hellar*  
 President - D. L. Hellar

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 29th day of August, 1968.

My Commission Expires: March 25, 1972.

*Catherine Darcey*  
 Notary Public - Catherine Darcey

