


WELL PLUGGING RECORD

All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ellis County. Sec. 29 Twp. 11 Rge. (E) 16 (W)
Location as "NE/CNW%SW%" or footage from lines NE $\frac{1}{4}$ SW $\frac{1}{4}$ NE $\frac{1}{4}$
Lease Owner Franco Central Oil Company
Lease Name Potter Well No. 11
Office Address 750 N Fourth Nat'l Bk Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 10-30-19 57
Application for plugging filed 10-30-19 57
Application for plugging approved 10-30-19 57
Plugging commenced 10-30-19 57
Plugging completed 10-30-19 57
Reason for abandonment of well or producing formation _____

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	974	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole to 600' with heavy mud. Set bottom plug with 20 sacks cement through drill pipe. Filled hole to 250', set middle plug with 20 sacks. Filled hole to 40' with heavy mud. Set top plug with 10 sacks cement, 1/2 sack kulls. Cement filled to base of cellar.

11/18/57

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Lewis Drilling Company
Address 915 Union Center, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
J. Fred Hambright (employee of owner) or (owner) or operator of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. Fred Hambright
915 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 4 day of November, 19 57

A. R. Derrington
(A. R. Derrington) Notary Public.

My commission expires 8-20-60

PLUGGING
SEC 29 T 11 R 16W
BOOK PAGE 58 LINE 28

WELL LOG

COMPANY Franco Central Oil Company

SEC. 29 T. 11 R. 16

FARM Potter

NO. 11

LOC. NE $\frac{1}{4}$ SW $\frac{1}{4}$ NE $\frac{1}{4}$

TOTAL DEPTH 3380

COMM. 10-21-57


COMP. 10-30-57

COUNTY Ellis
KANSAS

SHOT OR TREATED

CONTRACTOR Lewis Drilling Company

ISSUED



CASING

20	10
15	8 5/8" - 974'
12	6
13	5

ELEVATION 1787 K.B.

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

0-75	Post rock & shale
75-520	Shale
520-600	Sand
600-962	Red bed & shale
962-1010	Anhydrite
1010-1785	Shale & shells
1785-2274	Shale & Lime
2274-2490	Shale
2490-3380	Lime & shale
3380	Total Depth

Geologic Tops

Heebner	2965
Toronto	2990
Lansing KC	3015
B/KC	3258
Conglomerate	3324
Simpson Shale	3333
Arbuckle	3346

11/8/1957

PLUGGING
 SEC 29 T. 11 R. 16
 BOOK PAGE 58 LINE 28

State of Kansas
 County of Sedgwick } ss:

I, J. Fred Hambright of the Lewis Drilling Company
 upon oath state that the above and foregoing is a true and correct copy of the log of the Potter #11 well.

Subscribed and sworn to before me this 4 day of November 19 57

My Commission Expires: 8-20-60

A. R. Derrington
 (A. R. Derrington) NOTARY PUBLIC