

REW


15-051-02092-00-00

Form CP-4

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
7-19-1974
JUL 19 1974
CONSERVATION DIVISION
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Location as "NE/CNW/SE/SW" or footage from lines
County, Sec. 29 Twp. 11S Rge. (E) 16 (W)
SE SE NE

Lease Owner Ellis Mobil Oil Corporation
Lease Name Potter "A" Well No. 15
Office Address P. O. Box 1934, Oklahoma City, Oklahoma 73101
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 5-16 19 59
Application for plugging filed 10-8 19 73
Application for plugging approved 10-10 19 73
Plugging commenced 7-1 19 74
Plugging completed 7-9 19 74
Reason for abandonment of well or producing formation Uneconomical to produce, zone watered out.
If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Arbuckle Depth to top 3290 Bottom 3390 Total Depth of Well 3390 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Arbuckle	Oil & Water	3291	3314	8-5/8"	952	None
				5 1/2"	3389	2526

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Filled hole with sand from 3390-3375', capped sand with 4 sacks of cement. Set plug at 370'. Placed rock bridge from 370 to 350'. Ran 5 yards of cement from 350' to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Glenn Pipe Pulling
Address 204 E. 6th, Ellinwood, Kansas 67526

STATE OF Oklahoma COUNTY OF Oklahoma, ss.
Paul K. Langenberg (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul K. Langenberg
Box 1934, Oklahoma City, Oklahoma 73101
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of July, 19 74

Nancy Berry
Notary Public.

My commission expires May 9, 1978

