


15-051-01277-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Location as "NE/CNW/SW" or footage from lines NE/SW/SE  
County. Ellis Sec. 29 Twp. 11 Rge. 6 (E) 16 (W)  
Lease Owner Franco Central Oil Co.  
Lease Name Potter "C" Well No. 1  
Office Address 512 Fourth National Bank Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 6-8 1957  
Application for plugging filed 6-8 1957  
Application for plugging approved 6-8 1957  
Plugging commenced 6-8 1957  
Plugging completed 6-8 1957  
Reason for abandonment of well or producing formation \_\_\_\_\_



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1010'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.  
Filled hole with heavy mud to 500'. Set bottom plug with 1/3 sack hulls and 25 sacks cement thru drill pipe. Filled with mud to 40', set top plug with 1/3 sack hulls. Filled to base of cellar with 10 sack cement.

RECEIVED  
STATE CORPORATION COMMISSION  
6-20-1957  
JUN 20 1957  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Lewis Drilling Company  
Address 915 Union Center Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
J. Fred Hambright (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. Fred Hambright  
915 Union Center Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 13 day of June, 1957  
A. R. Derrington  
A. R. Derrington Notary Public.

My commission expires 8-20-60

PLUGGING  
FILE SEC 29 T 11 : 16W  
BOOK PAGE 20 LINE 42

WELL LOG

15-051-01277-00-00

COMPANY Franco Central Oil Company

SEC. 29 T. 11 R. 16  
LOC. NE/SW/SE

FARM Potter "C"

NO. 1

TOTAL DEPTH 3410'

COMM. 5-28-57


COMP. 6-8-57

COUNTY Ellis  
KANSAS

SHOT OR TREATED

CONTRACTOR Lewis Drilling Company

ISSUED



CASING

20	10
15	8 5/8" 1010'
12	6
13	5

ELEVATION 1815 R.B.

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

0-150	Shale & shells
150-475	Shale
475-580	Sand
580-745	Shale & shells
745-990	Red beds
990-1035	Anhydrite
1035-1450	Shale & red beds
1450-1630	Shale
1630-1895	Lime
1895-2005	Shale & lime
2005-2230	Lime
2230-2740	Lime & shale
2740-3410	Lime
3410	T. D.

Geologic Tops:

Heebner	2980
Kansas City	3029
B/Kansas City	3267
Conglomerate	3328
Arbuckle	3382

6-20-1957

PLUGGING  
SEC 29 T 11 R 16W  
BOOK PAGE 20 LINE 42

State of Kansas  
County of Sedgwick

ss:

I, J. Fred Hambright of the Lewis Drilling Company

upon state that the above and foregoing is a true and correct copy of the log of the Potter "C" #1 well.

*J. Fred Hambright*  
J. Fred Hambright

Subscribed and sworn to before me this 13 day of June 19 57

My Commission Expires: 8-20-60

*A. R. Derrington*  
A. R. Derrington NOTARY PUBLIC