

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Ellis County, Sec. 16 Twp. 11S Rge. 20W (E) (W)

Location as "NE/CNW/SW" or footage from lines NE NE NW

Lease Owner Imperial Oil of Kansas, Inc.

Lease Name Fischer "B" Well No. 1

Office Address 780 Fourth National Bldg., Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed June 29 1959

Application for plugging filed June 29 1959

Application for plugging approved June 29 1959

Plugging commenced June 29 1959

Plugging completed June 29 1959

Reason for abandonment of well or producing formation No commercial quantities of oil found.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3685 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 220' | 220' |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set No. 1 Plug at 550' with 20 sacks cement;
Set No. 2 Plug at 220' with 20 sacks cement;
Set No. 3 Plug at 40' with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Imperial Oil of Kansas, Inc.

Address 780 Fourth National Bldg., Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Stanley J. Bounds (employee of owner or contractor) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God, IMPERIAL OIL OF KANSAS, INC.

(Signature) BY: Stanley J. Bounds

780 Fourth National Bldg., Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 20th day of July, 1959

My commission expires July 7, 1962

Mona L. Latier Notary Public.

STATE 10-3-1959 OCT 3 1959

CONSERVATION DIVISION Wichita, Kansas

15-051-00350-00-00

DRILLER'S LOG

RECEIVED
STATE CORPORATION COMMISSION
10-3-1959
OCT 3 1959

Imperial Oil of Kansas, Inc.
780 Fourth National Building
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Fischer "B" No. 1
NE NE NW Sec. 16-11S-20W
Ellis County, Kansas

Total Depth: 3685'

Commenced: 6-18-59 Completed: 6-27-59

Elevation: 2032' K.B.
Production: D & A

Contractor: Imperial Oil of Kansas, Inc.
Wichita 2, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 220' with 150 sacks cement.

Figures indicate bottom of formations:

| | |
|---------------------|-------|
| Shale | 218' |
| Shale & Shells | 940' |
| Dakota sand | 1155' |
| Red Bed & Shale | 1458' |
| Anhydrite | 1504' |
| Shale | 1575' |
| Shale & Shells | 2020' |
| Shale & Lime | 3259' |
| Lime | 3665' |
| Lime & Conglomerate | 3685' |
| Total Depth | 3685' |

TOPS

| | |
|--------------------|----------------|
| Anhydrite | 1458' (/ 574) |
| Heebner | 3321' (-1289) |
| Toronto | 3345' (-1313) |
| Lansing | 3362' (-1330) |
| Rotary Total Depth | 3685' (-1653) |

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By: Stanley J. Bounds
Stanley J. Bounds, Vice-President

Subscribed and sworn to before me this 21st day of July, 1959.

My Commission Expires:

July 7, 1962

Mona L. Latier
Mona L. Latier-Notary Public

