

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Ellis County. Sec. 16 Twp 11S. Rge. (E) 20 (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines SE/4 SE/4 SE/4

Lease Owner W. L. Hartman

Lease Name King

Well No. 1

Office Address Box 54, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 9, 1946

Application for plugging filed April 9, 1946

Application for plugging approved April 9, 1946

Plugging commenced April 13, 1946

Plugging completed April 13, 1946

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production --- 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well H. W. Kerr

Producing formation --- Depth to top --- Bottom --- Total Depth of Well 3730 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS


CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface Pipe		0	153	10 3/4"	153'	0
Long String		0	3395	7"	3395'	626'
Long String		0	3453	5 1/2"	3453'	3453'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from --- feet to --- feet for each plug set.

Dumped 5 sacks cement on bottom (3730!); mudded back to 3400 with mud, rock and lead wool. Set rock bridge at 3400, mudded back to 130', set rock bridge and cemented with 5 sacks; mudded back to 10', cemented with 10 sacks, cement returning to surface.

FILED 16 11 20W
BOOK PAGE 51 LINE 18



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to W. L. Hartman
Address Box 54, Wichita, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

I, J. T. Phoenix, (employee of owner) ~~or (owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. T. Phoenix

Ellinwood, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 18th day of April, 1946.

J. Rader
Notary Public.

My commission expires July 7, 1948



W. L. Hartman, Owner - King #1

SE SE SE Section 16, Township 11 South, Range 20 West
Ellis County, Kansas

Figures indicate bottom of formation

	0	to	35	Post Rock
			153	Sand and Shale
			450	Shale and Shells
			1115	Sand, Shale and Shells
			1355	Sand and Shells
			1480	Shale and Red Bed
Pipe:			1485	Shale and Shells
			1530	Anhydrite
10 3/4" set at 153 feet			1945	Shale and Shells
7" set at 3395 feet			2225	Shale and Lime
			2345	Lime
			2430	Lime and Shale
			2610	Lime
Tops:			2700	Shale and Shells
			2765	Shale
Anhydrite	1485		2810	Lime and Shale
Kansas City	3379		2990	Lime
Arbuckle	3678		3060	Shale and Shells
			3110	Shale
			3185	Lime and Shale
			3350	Lime
			3390	Shale and Lime
Started February 17, 1946			3395	Lime
Rotary Completed March 2, 1946			3395	Total Rotary Depth

Cable Tool Work

Drilled cement and cleaned out to original rotary depth

			3419	Lime
			3427	Shale
			3442	Red Shale
			3453	Sand
			3477	Lime
			3482	Shale
			3494	Lime
Pipe:			3498	Shale
			3523	Lime
5 1/2" run to 3453' (not cemented)			3527	Shale
			3580	Lime
			3583	Red Rock
			3601	Lime
			3610	Shale
Water Record:			3613	Lime
			3615	Shale
10 b.w.	3442		3626	Vari-colored Shale
			3628	Hard Lime
			3635	Shale
			3640	Lime
			3645	Shale
			3654	Lime
			3658	Shale
			3660	Lime
			3665	Shale
			3670	Lime
			3675	Shale
			3699	Lime
Completed Cable Tool Work April 13, 1946			3730	Chert
			3730	Total Depth D & A

16 11 20W
51 18

4-23-1946
APR 23 1946

State of Kansas)
County of Barton) ss

I, G. W. Keyes, partner of G. W. Keyes Drilling Company, Drilling Contractor of the above-described well, being first duly sworn on oath, declare: That I have knowledge of the facts, statements and matters herein contained pertaining to the log of the above-described well as filed and that the same are true and correct.

Subscribed and Sworn to before me this 18th day of April 1946.

G. W. Keyes
J. J. Rader
Notary Public

My commission expires July 7, 1948.