


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

15-051-01257-00-00  
WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

County. Sec. 17 Twp. 11 Rge. 20 West (W)  
Location as "NE/CNW/SW" or footage from lines C N/2 NW NW  
Lease Owner W J Coppinger et al  
Lease Name Thayer Well No. 1  
Office Address 507 Union Natl Bldg., Wichita, Ks.  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed March 4, 19 57  
Application for plugging filed same 19  
Application for plugging approved same 19  
Plugging commenced same 19  
Plugging completed same 19  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3650 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	330	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with mud laden fluid;  
Pumped in 100 sacks pozmix cement under pressure with  
Halliburton Oil Well Cementing Company equipment.  
Cemented surface pipe up to cellar

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Coppinger Drilling, Inc  
Address Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
W. J. Coppinger (employee or owner) of (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W J Coppinger  
507 Union Natl Bldg., Wichita  
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of March 19 57

My commission expires March 7, 1960 (Mayree Broaddus) Notary Public.

PLUGGING  
FILE SEC. 17 T. 11 R. 20  
BOOK PAGE 146 LINE 3

MAR 7 - 1957  
3-7-1957  
CONSERVATION DIVISION  
Wichita, Kansas

15-051-01257-00-00

DRILLERS LOG

Contractor: Coppinger Drilling, Inc.  
507 Union National Building  
Wichita, Kansas

Coppinger Drilling, Inc., et al  
Thayer #1 - C N/2 NW NW  
Section 17-11S-20W  
Ellis County, Kansas

Drilling Commenced: 2/18/57  
Drilling Completed: 3/4/57

Elevation: 2023' R. B.  
2021' D. F.  
2019' G. L.

Sand	85
Blue Shale	200
Shale	490
Shale & Lime	600
Shale	1005
Sand	1150
Shale	1230
Shale & Shells	1480
Anhydrite	1517
Shale	1580
Lime & Shale	2140
Lime	2210
Lime & Shale	2325
Lime	2470
Lime & Shale	2490
Shale	2755
Shale & Lime	2930
Shale	3015
Lime & Shale	3260
Lime	3544
Lime & Shale	3582
Chert	3593
Lime & Chert	3621
Chert	3627
Lime - Arbuckle	3630
Arbuckle Lime	3650
R. T. D.	3650

Casing Record

8 5/8" set at 330' w/225 sax regular cement.

Logs

Anhydrite	1480'
Topeka	3069' (-1046')
Hoebner	3281' (-1258')
Toronto	3304' (-1281')
Lansing	3320' (-1297')
Base Kansas City	3532' (-1509')
Conglomerate	3582' (-1559')
Simpson	3603' (-1585')
Arbuckle	3626' (-1603')

R. T. D. 3650'

State of Kansas  
County of Sedgwick, ss.

I hereby certify that the foregoing is a true and correct log of the #1 Thayer drilled at the above location by Coppinger Drilling, Inc., to the best of my knowledge and belief.

*Lee Paulsen*  
Lee Paulsen, Geologist

Subscribed and sworn to before me, a notary public,  
this 5th day of March, 1957.

My commission expires: March 7, 1960

*Marcel E. Caddus*  
Marcel E. Caddus, Notary Public

RECEIVED  
STATE CORPORATION COMMISSION

3-7-1957  
MAR 7 - 1957

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING			
FILE	SEC	T	R
	17	11	20W
BOOK	PAGE	LINE	
	146	3	