


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Trego County, Sec. 26 Twp. 11S Rge. 23W ~~XE~~ (W)  
Location as "NE/CNW/SW" or footage from lines NW NW NW

Lease Owner Okmar Oil Co.  
Lease Name Howat Well No. 1  
Office Address 1130 Wichita Plaza, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 12-10-67 19\_\_  
Application for plugging filed 12-10-67 19\_\_  
Application for plugging approved 12-10-67 19\_\_  
Plugging commenced 12-10-67 19\_\_  
Plugging completed 12-10-67 19\_\_  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3900 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	230'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

100 sks. Posmix @ 975', 20 sks. Posmix @ 240', bridged plug @ 40' with 1/2 sk. hulls, 10 sks. Posmix

RECEIVED  
12-18-1967  
DEC 18 1967

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.  
Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.

Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

Box 486, Great Bend, Kansas 67530  
(Address)

SUBSCRIBED AND SWORN to before me this 15th day of December, 19 67

My commission expires April 1, 1971

Ulanda Nichols  
Notary Public.

15-195-20050-00-00

12-18-1967  
DEC 18 1967

DRILLER'S LOG

REGISTRATION DIVISION  
Kansas

COMPANY:	Okmar Oil Company
CONTRACTOR:	LEBEN DRILLING, INC.
FARM:	HOWAT #1
LOCATION:	NW NW NW SECTION 26-11S-23W TREGO COUNTY, KANSAS
COMMENCED:	12-2-67
COMPLETED:	12-10-67

-----		
0	230	Shale
230	910	Shale, Sand
910	1250	Shale, Sand, Shale
1250	1864	Shale, Sand, Redbed
1864	1908	Anhydrite
1908	1950	Shale, Redbed
1950	2798	Shale, Lime
2798	3160	Lime, Shale
3160	3485	Shale, Lime
3485	3650	Lime, Shale
3650	<u>3900</u>	<u>RTD - D. &amp; A. (Lime Formation)</u>

-----  
8 5/8" 8 rd. 24# used surface casing set @ 230' cemented with 175 sacks Sunset

-----  
I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Howat #1 Well, located NW NW NW of Section 26-Township 11 South-Range 23 West-Trego County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS )  
                          ) SS  
COUNTY OF BARTON )

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 15th day of December, 1967.

Ulanda Nichols

Ulanda Nichols



My Commission Expires:  
April 1, 1971