

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

009-00532-0000

Lease Operator: Herman L. Loeb LLC
Address: P.O. Box 838 Lawrenceville, IL 62439
Phone: (812) 453-0385 Operator License #: 3273
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 3/17/2009 (Date)
by: Case Morris (KCC District Agent's Name)
Is ACO-1 filed? ☒ Yes ☐ No If not, is well log attached? ☐ Yes ☒ No
Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: 3404' Bottom: 3414' T.D. 3505'
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - Completed 2/15/1957
Lease Name: Hulme
Well Number: A-1
Spot Location (QQQQ): NE - NE - SW -
2310 Feet from ☐ North / ☒ South Section Line KCC
2970 Feet from ☒ East / ☐ West Section Line PKT
Sec. 21 Twp. 20 S. R. 12 ☐ East ☒ West
County: Barton
Date Well Completed: 2/15/1957
Plugging Commenced: 3/12/2009
Plugging Completed: 3/18/2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	210	0
				5 1/2"	3505'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Mill down to 499' w/ shark nose mill and determined that we are outside of casing @ 330'. Ran tbg to 470', mixed and pumped 220 sxs 60/40

4% and circulated cement to surface. Laid down tbg. Pumped thru 5 1/2" 60 sxs and circulated cement through 8 5/8".

SI 8 5/8' and pumped 120 more sxs w 500# CSH 60/40 4% gel. Tagged cement @ 60', cut off 8 5/8" and 5 1/2", filled 2 yds Redi Mix.

Name of Plugging Contractor: Pratt Well Service License #: 5893

Address: P.O. Box 847 Pratt, KS 67124-0847

RECEIVED
KANSAS CORPORATION COMMISSION


MAR 24 2009

Name of Party Responsible for Plugging Fees: Herman L. Loeb

State of Kansas County, Barton, ss.

CONSERVATION DIVISION
WICHITA, KS

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Alan V. Smith

(Address) 509 N. Cedar, Medicine Lodge, KS 67104

SUBSCRIBED and SWORN TO before me this 23 day of March, 20

Glenda Morrison
Notary Public

My Commission Expires: 11/30/12

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT