

Notice: Fill out COMPLETELY  
and return to Conservation Division  
at the address below within  
60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: F. G. Holl Company L.L.C.  
Address: 9431 E Central Suite #100, Wichita, KS 67206  
Phone: (316) 684-8481 Operator License #: 5056  
Type of Well: Oil KCCPTPm CP213 Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: \_\_\_\_\_ (Date)  
by: Case Morris (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 009-25, 147-0000  
Lease Name: Taylor Trusts  
Well Number: 1-10  
Spot Location (QQQQ): \_\_\_\_\_ - C - SW - SE  
770 Feet from  North /  South Section Line  
2200 Feet from  East /  West Section Line  
Sec. 10 Twp. 20 S. R. 14  East  West  
County: Barton  
Date Well Completed: 1-11-08  
Plugging Commenced: 2-27-09  
Plugging Completed: 3-2-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	800	
				5 1/2	3699	2600

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Dug cellar, raised pole, checked hole, sanded off bottom, loaded hole with water, unpacked casing head, set floor, pulled slips, had 24" stretch, sand was at 3480', bailed 5 sacks cement with bailer, ripped casing at 2810', worked pipe, ripped casing at 2600', pipe came free, pulled casing up to 1550', pumped 15 sacks, 300# hulls, pulled to 850', pumped 40 sacks, 100# hulls, pulled to 400', circulated with 100 sacks, 100# hulls to surface, pulled rest of casing.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925  
Address: 190 US Highway 56, Ellinwood, KS 67526

RECEIVED  
KANSAS CORPORATION COMMISSION


MAR 25 2009

Name of Party Responsible for Plugging Fees: F.G. Holl Company L.L.C.  
State of Kansas County, Sedgwick, ss.

CONSERVATION DIVISION  
WICHITA, KS

Loveness Mpanje (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Loveness Mpanje  
(Address) 9431 E. Central, Suite 100, Wichita, Kansas 67206



SUBSCRIBED and SWORN TO before me this 24th day of March 2009, at \_\_\_\_\_  
Betty H. Spotswood My Commission Expires: 04/30/2010

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*Handwritten initials*