

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-04921-00-00
Spot: NWSWNE Sec/Twnshp/Rge: 21-20S-12W
3630 feet from S Section Line, 2310 feet from E Section Line
Lease Name: HULME B Well #: 8
County: BARTON Total Vertical Depth: 3485 feet

Operator License No.: 3273
Op Name: LOEB, HERMAN L.
Address: PO BOX 524
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3484	0	w/unknown sxs cmt
SURF	8.625	254	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/20/2009 2:00 PM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: GEORGE PAYNE Company: LOEB, HERMAN L. Phone: (812) 853-3813

Proposed Plugging Method: Ordered 500 sxs 60/40 pozmix - 4% gel - 500# hulls.
Old hole - ran tubing to 501' - drilled 630' - ran camera down hole outside casing at 500'.
Ran open end tubing down hole to 620'.
113.26

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/23/2009 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

03/20/2009 - Ran tubing to 620' - pumped 50 sxs cement - pump truck broke down - flushed hole with 100 bbl's fresh water - no cement circulated to surface - shut down.
03/23/2009 - Ran tubing to 585' - pumped water to test flow rate - about 2 bbl's a minute. Started pumping cement.
Pumped 350 sxs cement - circulated cement to surface.
Pulled tubing - tied to casing - pumped 60 sxs cement - circulated out backside.
Shut in backside - pumped 50 sxs cement with 250# hulls.
Max. P.S.I. 400#. Shut in.

Perfs:

INVOICED
DATE 4-21-09
INV. NO. 2009061413

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 26 2009

CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN) CM

MAR 24 2009

per

HONAKER-DAVIS DRILLING CO #8 HULME 'B'

21-20-12W 53
NW SW NE

Contr. _____ BARTON County

E 1849 Comm. _____ Comp. 4-4-58 IP _____ 201 BOPD, NW


Tops	Depth	Datum
ANH	627	1222
TOP	2870	-1021
HEEB	3027	-1178
BR LM	3146	-1297
KC	3161	-1312
CONG	3393	-1544
ERO ARB	3402	-1553
ARB	3414	-1565
TD	3485	-1636

Casing

8" 254
5" 3484

NO TESTS
PERF 3442-50: 10 BOPH

WORKMAN NW POOL



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS