

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-00532-00-00

Spot: NENESW

Sec/Twnshp/Rge: 21-20S-12W

2310 feet from S Section Line,

2970 feet from E Section Line

Lease Name: HULME A

Well #: 1

County: BARTON

Total Vertical Depth: 3505 feet

Operator License No.: 3273

Op Name: LOEB, HERMAN L.

Address: PO BOX 524

LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3504	0	w/unknown sxs cmt
SURF	8.625	210	0	w/unknown sxs cmt

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 03/17/2009 8:00 AM

Plug Co. License No.: 5893

Plug Co. Name: PRATT WELL SERVICE, INC.

Proposal Rcvd. from: M.L. COX

Company: LOEB, HERMAN L.

Phone: (620) 786-2009

Proposed
Plugging
Method:

Ordered 450 sxs 60/40 pozmix - 4% gel - 400# hulls.
Well abandoned in 1982.
Started in well with 2 3/8" tubing stacked out at 332'.
Went in with mill - got to 499' - losing fluid - could not go any deeper.

113.91

Plugging Proposal Received By: CASE MORRIS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 03/17/2009 1:30 PM

KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Ran tubing to 470' - pumped 220 sxs cement - circulated to surface.
Pulled tubing - tied to casing - opened backside - pumped 30 sxs cement - circulated out backside.
Closed backside - pumped 150 sxs cement with 300# hulls.
Max. P.S.I. 300#. Shut in.

INVOICED
DATE 4-21-09
INV. NO. 2009061413

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 26 2009

CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #33316.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

Form CP-2/3

MAR 24 2009

HONAKER-DAVIS DRILLING

#1 HULME 'A'

21-20-12W

NE NE SW

53

Contr. HONAKER-DAVIS DRG

BARTON

County

E 1849RB Comm. 1-5-57 Comp. 4-12-57 IP 328 BOPD/ARB

PHY POT

Tops	Depth	Datum
HEEB	3033	-1184
LANS	3170	-1321
ARB	3402	-1553
ID	3505	-1656

Casing

8" 210

5" 3504

DST 3172-3200/20", 5' MUD

BHP 600#

DST 3406-12/38", 15' MUD, V SL

OC, BHP 680#


DST 3437-45/1 HR, 1040' OIL,

BHP 1050#

WORKMAN NW POOL PERF 30/3438-

48: ACID 500

SWB 10 BOPH



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS