

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22451-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 13-11S-24W
330 feet from S Section Line, 2297 feet from E Section Line
Lease Name: VREELAND Well #: 4
County: TREGO Total Vertical Depth: 4021 feet

Operator License No.: 33657
Op Name: OHIO KENTUCKY OIL CORPORATION
Address: THE WILLIAM M GRIFFITH BUILDING
LEXINGTON, KY 40503

String	Size	Depth (ft)	Pulled (ft)	Comment
PC		1975		
PKR		3891		
PROD	4.5	4006	0	w/175 sxs cmt
SURF	8.625	220	0	w/175 sxs cmt
T1	2.375	2037		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/20/2009 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID FUNK Company: OHIO KENTUCKY OIL CORPORAT Phone: (859) 276-3500

Proposed Plugging Method: Ordered 285 sxs 60/40 pozmix - 4% gel - 800# hulls - 9 sxs gel.
DV Tool at 1972' w/350 sxs cement.
130.68

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/20/2009 12:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied onto casing - pumped 50 sxs cement with 400# hulls.
Waited 30 minutes - pumped 9 sxs gel.
Pumped 70 sxs cement with 200# hulls - still on vacuum - let set 45 minutes.
Pumped 40 sxs cement. Max. P.S.I. 100#.
Tied onto backside. Max. P.S.I. 150#.

Perfs:

Top	Bot	Thru	Comments
3905	3910		

INVOICED


DATE 4-21-09
INV. NO. 2009061417

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 24 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: LEASE ORIGINALLY KNOWN AS GALEN GEYER #5. QUALITY OILWELL CEMENTING-TICKET #3041.

Plugged through: CSG

District: 04

Signed 
(TECHNICIAN)

CM

PST

MAR 23 2009

OHIO KENTUCKY OIL CORP
LEXINGTON KY 40503

IRELAND #4

#5 GEYER, GALEN

13-11S-24W
330'FSL & 2297'FEL, SEC (IRREG)
KANSAS

City: TREGO

Spot: E2 SW SW SE

API 15-195-22451

Site: 3-1/2 N & 2-1/2 W OF WAKEENEY KS

Lat/Long: 39.08906 -99.93388

Field: W-L SOUTH EXT (1/4 E)

OIL

FR: 04/20/2007 Spd: 09/07/2007 Drig Cp: 09/14/2007 Issued: 05/12/2008 Revised: 05/12/2008

Copyright 2008 Independent Oil & Gas Service, Inc. Wichita, KS

Side 1

IP Status:

OIL, LKC, INTV NA, 12/1/2007

Contr: WW DRILLING #6

Elev: 2355 GL

Formation Tops: (L-Log, S-Sample, D-Driller)

NO TOPS RPTD

LOGGED

RTD

4021 -1666

Csg: 8-5/8" 200+ (ALT 2), PROD CSG NA

Finds:

COMMENT: ACTUAL STAKED ELEV IS 2355.4 GL;

PROPOSED START 6/1/2007

NO CORES

DSTS TAKEN - DETAILS NA

Comp Info: TRGT ZN: LKC, MISS (OIL), PTD 4250

(MISS), MICT (10/1/2007) - CO, PF (LKC) INTV NA,

SWB DWN, GSO, POP, OIL WELL (POTENTIAL

NOT RPTD), 12/1/2007 - TIGHT HOLE - NO OTHER

INFO AVAILABLE - TEMP COMP 5/12/2008