

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-20171-00-01
Spot: SWSWNE Sec/Twnshp/Rge: 10-31S-9W
2310 feet from N Section Line, 2310 feet from E Section Line
Lease Name: KIRKPATRICK OWWO Well #: 1
County: HARPER Total Vertical Depth: 4406 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4447	2080	100 SX
SURF	8.625	254		225 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/13/2009 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: PUMP 25 SKS ON BOTTOM. RECOVER CASING. 35 SKS 1500', 35 SKS 1000', CIRC 305-0'.
143.20

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 03/13/2009 11:30 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE SQUEEZED OFF WITH 25 SKS OF CMT, AND TAGGED AT 4275'. THE CASING WAS RECOVERED FROM 2080 AND PULLED TO 1500', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 1000', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 305', WHERE CMT WAS CIRCULATED TO SURFACE. THE REMAINING CASING WAS PULLED AND THE CASING WAS TOPPED OFF.

Perfs:

Top	Bot	Thru	Comments
4372	4378		MISS

INVOICED

DATE 4-21-09
INV. NO. 2009061418

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 26 2009

Remarks: QUALITY WELL CEMENTING 60/40 4% GEL

Plugged through: CSG

District: 02

Signed [Signature]
(TECHNICIAN) PKT