

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-129-20780-00-00  
Spot: NW Sec/Twnshp/Rge: 33-31S-42W  
3960 feet from S Section Line, 3960 feet from E Section Line  
Lease Name: BOYD Well #: 1-33  
County: MORTON Total Vertical Depth: 5400 feet

Operator License No.: 8061  
Op Name: OIL PRODUCERS INC. OF KANSAS  
Address: 1710 WATERFRONT PKWY  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	5220	2450	WITH 250 SX CMT
SURF	8.625	1524		WITH 760 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/25/2009 9:00 AM  
Plug Co. License No.: 34091 Plug Co. Name: BLACKHAWK WELL SERVICE, LLC  
Proposal Rcvd. from: BARRY WALTERS Company: BLACKHAWK WELL SERVICE, LL Phone: (785) 623-1066

Proposed Plugging Method: PUMP 200# HULLS & 50 SX CMT AT 4950'. PLUG AT 1530' WITH GEL & 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT

175.50

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/25/2009 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 200# HULLS & 50 SX CMT AT 4950' THROUGH TBG. 1ST PLUG AT 1836' WITH GEL & 50 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4966	4984		MORROW

INVOICED  
DATE 4-21-09  
INV. NO. 2009061418

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAR 23 2009  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

RECEIVED  
MAR 10 2009  
KCC DODGE CITY

Signed

*Ken Jehlik*  
(TECHNICIAN)

PKT  
Form CP 273