

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-21347-00-01
Spot: SENWNW Sec/Twnshp/Rge: 7-21S-24W
4518 feet from S Section Line, 4002 feet from E Section Line
Lease Name: KING Well #: 1
County: HODGEMAN Total Vertical Depth: 4417 feet

Operator License No.: 5123
Op Name: PICKRELL DRILLING COMPANY, INC.
Address: 100 S MAIN STE 505
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3850		WITH 2 SX CMT
CIBP		4165		
CIBP		4380		
DVT		1510		WITH 350 SX CMT
PROD 4.5		4409	0	WITH 150 SX CMT
SURF 8.625		253		WITH 160 SX CMT

Well Type: SWD UIC Docket No: D26615.0 Date/Time to Plug: 03/10/2009 1:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: ED MONDERO Company: PICKRELL DRILLING Phone: (316) 262-8427

Proposed Plugging Method: PUMP 300# HULLS & 50 SX CMT. CIRCULATE CMT TO SURFACE FROM 1530-0' CHECK ANNULUS.

143.55

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/10/2009 4:30 PM KCC Agent: LINDLEY REIMER

Actual Plugging Report:

CIBP @ 3850' & 2 SX CMT. 1ST PLUG TIED ONTO BACKSIDE & PUMPED 12 SX CMT INTO 8 5/8" ANNULUS WITH 300# PRESSURE. 2ND PLUG CIRCULATED 100 SX CMT THROUGH TBG FROM 1500' TO SURFACE. 3RD PLUG PULLED OUT OF HOLE W/TBG. TOPPED OFF 4 1/2" WITH ADDITIONAL CMT.

Perfs:

Top	Bot	Thru	Comments
4198	4202		MARM
4081	4086		KC
4008	4012		KC
3910	3918		KC

INVOICED
DATE 4-21-09
INV. NO. 2009061419

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 23 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

Plugged through: TBG

District: 01
RECEIVED
MAR 12 2009
KCC DODGE CITY

Signed [Signature]
(TECHNICIAN)